DRILLING & BLASTING OF SOLID ROCK SUBGRADE – ITEM 114 MOD.
STA. 2251+00 TO 2267+00

PLANTING TREES, SHRUBS AND VINES – ITEM 631
SEE SHADED AREAS AND QUANTITY SHEET

CLEARING & TRIMMING ITEM 601
SEE NOTES "SAVE"

PAVED DITCH ITEM 554 *
RAMP "A" STA. 201+94 TO 211+19 RT.
RAMP "B" STA. 12+02 TO 12+27 LT. & RT.
STA. 2254+52 TO 2254+77 MED.
STA. 2263+73 TO 2263+98 MED.
STA. 2266+68 TO 2266+93 MED.

GRANITE SLOPE EDGING ITEM 556-A *
RAMP "A" BULLNOSE

THREE CABLE GUARD RAIL WITH STEEL POSTS ITEM 543 *
STA. 2251+00 TO 2254+70 S.B. LT.
STA. 2254+75 TO 2256+51 N.B. RT.

* STAGE 2 ITEMS

FED. ROAD DIV. No.	STATE	FEDERAL PROJECT No.	SHEET	TOTAL SHEETS
	VERMONT	I-89-3(15)	15	150

PROPERTY LINE FENCE ITEM 583
STA. 2251+00 TO 2267+00 RT
2267+00 RT – 2267+00 LT ±
FENCE TO BE ERECTED PRIOR TO CONSTRUCTION

QUARRY
PASTURE
RAMP "A"
RAMP "B"
SOUTH BOUND
NORTH BOUND
INTERSTATE 224
SAVE
LIMIT R.O.W.
CATTLE LANE
MEADOW
NORTHERN RED OAK
RED MAPLE
ROW Fence
ROW Fence
R.O.W. Fence
Treated Shldr.
Untreated Shldr.
FIELD ROAD
SHEET 14 MATCH LINE

B.M. # 197
EL. 383.46
S. I. T.

B.M. # 196
EL. 367.28
BOULDER

B.M. # 3
EL. 372.44

PARCEL 908
GRANTOR MARION A. & THELMA L. LYONS
STATIONS 2248+18 – 2252+55
TAKING 26 A±
REMAINDER NONE
RIGHTS NONE

TITLE TAKEN. COND 5/13/61
RECORDED: COLCHESTER – BK. 11 – PG. 176 – 5/13/61

PARCEL 906 D
STATIONS 2248+80 – 2285+15 SB
TAKING 30.0 A±

N.B. CURVE No. 2
Δ = 54°-57'-00" Rt.
D = 2°-00'
R = 2864.79'
L = 2747.50'
T = 1489.75'
E = 364.17'
Bank 11/16" per Ft.

S.B. CURVE No. 2
Δ = 54°-57'-00" Rt.
D = 2°-00'
R = 2864.79'
L = 2747.50'
T = 1489.75'
E = 364.17'
Bank 11/16" per Ft.

STA. 2267+00 N.B. & S.B.
END PROJECT I-89-3(15)
BEGIN PROJECT I-89-3(16)
END PROJECT I-89-3(22)

NOTE:
FOR N.B. & S.B. PROFILE SEE SHEET # 21

STAGE 2 CONSTRUCTION
STAGE 1 CONSTRUCTION

STATE OF VERMONT
DEPARTMENT OF HIGHWAYS

INTERSTATE PROJECT IN
WINOOSKI, COLCHESTER

PLAN
STA. 2251+00 TO STA. 2267+00

BOSWELL ENGINEERING CO. RIDGEFIELD PARK, N.J.

DRAWN BY V.R.K. | IN CHARGE R.K.
CHECKED BY E.P.C. | DATE
SCALE 1 IN. = 50 FT.
PROJECT NO. I-89-3(15) | SHEET 15 OF 150

STAGE 2 CONSTRUCTION I 89-3(22)
SHEET 13 OF 85

10