PROPERTY LINE FENCE W/STEEL POSTS, MOD
ITEM 583-II
SB 3204+00 - 3220+00 Lt.
NB 3204+00 - 3220+00 Rt.

* ~~DIT. CONC. CURB~~
~~ITEM 655-Type II~~
SB 3204+00 - 3206+50 Lt.

* JUTE MATTING - ITEM 623
SB 3205+25 - 3209+00 Rt.
NB 3204+00 - 3205+25 Rt.
SB 3210+50 - 3218+50 Rt.

DRILLING & BLASTING OF SOLID ROCK SUBGRADE ITEM 115
NB 3215+50 - 3220+00
SB 3208+00 - 3210+50
SB 3217+50 - 3220+00

* THREE CABLE GUARD RAIL W/ LIGHT STEEL POSTS, ITEM 538
NB 3214+50 - 3220+00 Lt.
SB 3204+00 - 3220+00 Lt.
NB 3204+00 - 3206+50 Lt.

INDIVIDUAL WATER SOURCES
NAT. SPRING N.B.L. 3205± - 2900' ±RT
NAT. SPRING N.B.L. 3208± - 1700' ±RT
NOTE: * DENOTES ITEMS TO BE INCLUDED IN STAGE II CONSTRUCTION.

Refer to special agreement with railroad for work to be performed by others within railroad R.O.W.

R.R. Trav. P.O.T. 310+35.04

PI. 307+60.73
Δ 9°06'80" Lt.

BM # 143
ASMD ELEV
554.415

BM # 144
ASMD ELEV
581.925

Scattered Pines & Brush

Sugar Bush

N 0°35'50" E

N 1°14'06" E

Rev. S.B. Curve Data
Δ 14°30'00" Lt.
D 0°24'
R 14,323.95
T 1,822.24
L 3,625.00
E 115.45
Bank 1/4 per ft.

CONTROL OF ACCESS IS COMPLETE ON THIS SHEET.

PLAN SCALE
0 50 100
100 FEET

Stage 2 Construction

GEORGIA-FAIRFAX-FAIRFIELD-ST. ALBANS
I 89-3 (41)
Sheet 69 of 213

65