PROPERTY LINE FENCE w/STEEL POSTS, MOD. ITEM 583-II
SB 3236+00 - 3252+00 Lt.
NB 3236+00 - 3252+00 Rt.

DEMOLITION & DISPOSAL OF BUILDING, ITEM 506
NB 3243 + 00 Rt.

* STD. STEEL BEAM GUARD RAIL WITH LIGHT STEEL POSTS, ITEM 545-A (12'6" c/c)
NB 3243+05 - 3244+59 Rt.
SB 3242+11 - 3243+65 Lt.
SB 3242+30 - 3243+84 Lt.
NB 3242+50 - 3244+12 Lt.

*THREE CABLE GUARD RAIL W/ LIGHT STEEL POSTS, ITEM 538
SB 3236+00 - 3237+09 Lt.
NB 3241+81 - 3252+00 Lt.

Rev. SB
P.I. 3242 + 15.32
3242 + 08.87

BM #146
ASMD ELEV
626.436

BM #147
ASMD ELEV
616.487

BM #148
ASMD ELEV
615.517

SB N 0°36'50" E

SB N. 11° 25' 50" E.

NB N3°28'20" E

NB N 7°14'44" E

NB N8°06'50" E

Rev. N.B.

Rev. S.B.

MATCH LINE

MATCH

SB 3244+30 - 3242+80 Rt.
Special Ditch - Item 103

SB 3242+30 Lt. - 3243+54 Rt.
New 48" x 108' RCCP, MP, 12 Gage

SB 3242+30 Lt. - 3243+35 Rt.
New 6" x 108' Pipe w/FD, Item 531-II

SB 3242+84 Rt. - NB 3243+93 Lt.
Special Ditch, Item 106
Riprap (light type) Item 513-B

SB 3242+95 - 3247+25 Rt.
New 6" x 486' Underdr. w/FD, Item 521-I

SB 3243+35 - 3247+25 Rt.
New 6" x 390' Underdr. w/FD, Item 521-I

STONE FILL FOR SLOPE PROTECTION, ITEM 512
SB 3242+60 - 3242+80 Rt.
SB 3242+88 - 3243+08 Rt.

RIPRAP (Light Type)
Item 513-B
SB 3242+80 - 3242+88 Rt.

INDIVIDUAL WATER SOURCES
DUG SPRING N.B.L. 3246± - 1000'± RT
DUG SPRING S.B.L. 3251+50 - 1100'± LT

DRILLING & BLASTING OF SOLID ROCK SUBGRADE, ITEM 115
SB 3236+00 - 3247+68
NB 3236+00 - 3239+68
SB 3236+10 - 3242+50

NOTE: * DENOTES ITEMS TO BE INCLUDED IN STAGE II CONSTRUCTION

SB 3247+39 Lt.
New 36" x 92' RCCP, Class III

SB 3247+30 Lt. - 3247+90 Rt.
110' New 6" x 86' Pipe, Item 531-II, w/FD

SB 3247+91 - 3251+90 Lt.
New 6" x 440' Und., Item 521-I, w/FD

SB 3247+90 - 3251+90 Rt.
New 6" x 400' Und., Item 521-I, w/FD

SB POST 3248+27.53

SB 3251+19 Lt. - 3252+00 Rt.
New 30" x 96' RCCP, Class III

V.T. GRID

P.I. 3249 + 45.50
3249 + 44.27

NOTE: See sheet 72 of 467 for plan details of N.B. Rest Area

Pipe Line To Sugar Hse.

Sugar Hse.

Rev. S.B.
Δ 10° 49' 00" Rt.
D 0° 30'
R 11,459.16
T 1084.89
L 2163.83
E 57.28
Bank 1/4" per ft.

NB 3243+00 - 3243+40 Rt.
New 6" x 100' Und., Item 521-I A

NB 3244+50 - 3244+86 Rt. Skew 70° Rt.
NB 3244+50 - 3244+86 Rt.
New 48" x 74' RCCP, MP, 12 Gage
70°

NB 3244+50 NB - 3243+25 SB.
Install 4" x 265' sleeve for water pipe, ¾" x 970' seamless copper water tube with 2 expansion service loops with key shut-off, Items 451, 594-B & 596

3247+30 - SB Rt. - 3247+72 - NB Lt.
Special Ditch - Item 106
Riprap (light type) ITEM 513-B

NB 3247+78 Rt.
New 30" x 84' R.C.P. Class III

NB 3248+00 - 3248+40 Rt.
New 6" x 100' Und., Item 521-I A

Curve Data
Δ 4° 38' 30" Rt.
D 0° 15' 00"
R 22,918.32
T 928.95
L 1856.67
E 18.80

APPROX. AERIAL UTILITY RELOCATION ROUTE BY VT ELECTRIC COOP, INC.

PLAN SCALE
0 50 100
100 FEET

CONTROL OF ACCESS IS COMPLETE ON THIS SHEET.

RELOCATION BEGINS 365' RT. OF POLE NO. 22 @ POLE NO. 21.

SB 3250+62.85 Lt.
New 30" x 96' R.C.P. Class III

SB 3250+00 - SB Rt. - 3252+20 - NB Lt.
Const. Special Ditch - Item 106
Riprap (light type) Item 513-B

NB 3252+20 - 3252+00 Lt.
New 30" x 96' R.C.P. Class III

Stage 2 Construction

GEORGIA-FAIRFAX-FAIRFIELD-ST. ALBANS
I 89-3 (41)
Sheet 73 of 213

| PLAN | | | |
|---|---|---|---|
| | SURVEYED | By: | DATE |
| | DESIGNED | Sowdoing | 11/82 |
| | ALIGNMENT | Crosby | 1/83 |
| NOTE BOOK | CHECKED | | |
| NO. | P.D.W. CHECKED | | |
| | TRACED | Ewell | 2/83 |

68