



Property Line Fence With Steel Posts
Item No. 583 - B
754+00 to 770+00 LT.
754+00 to 770+00 RT.

Paved Median Curb
Item No. 361-B
755+75 To 756+00 ✓
760+75 To 761+00 ✓
765+25 To 766+00 ✓

CONSTRUCT R.O.W FENCE
ACCORDING TO PLANS AND SPECS.
BEFORE CONSTRUCTION IS BEGUN
768+66 - 770+00 LT.
768+77 - 770+00 RT.

Bituminous Concrete Curb
Item No. 555
7585+00 to 761+00 RT.
757+85 to 7683+283 LT.
758+00 to 770+00 RT.

Three Cable Guard Rail With Steel Posts
754+00 To 756+77 RT. Median
7585+00 to 761+00 RT.
757+85 to 7683+283 LT.
758+00 to 770+00 RT.

Bituminous Grouted Stone Gutter
754+00 to 755+00 ✓
755+00 to 756+00 ✓
759+00 to 760+00 ✓
761+00 to 762+00 ✓

STATE	FED. AID PROJECT NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
VT.	I-91-1(9)	WAR	44	530

CURVE DATA for
LEFT LANE
Δ = 2° 06' 00" L
D = 0° 14' 00" R
R = 24.855 ft.
L = 318.17 ft.
E = 4.12
DO NOT BANK

U-Turn
761+50

Note: Location of Underdrain to be determined by the Engineer

#12A-EDWARD M. & GUSTIE A. SIMEON & CHARLES A. & ADA M. SIMEON
(A.S.S.) STA. 765+66-774+96.1
DITCH RIGHTS - STA. 773+75 ± LT. & RT.
COND. 6/9/59
REC: DUMMERSTON BK. 37 Pg. 181 - 6/9/59

STATE OF VERMONT
DEPARTMENT OF HIGHWAYS
INTERSTATE PROJECT in the towns of
BRATTLEBORO - DUMMERSTON - PUTNEY

THE CLARKESON ENGINEERING CO., INC.
CONSULTING ENGINEERS
BOSTON MASSACHUSETTS 3

SURVEYED BY *Roger* CHECKED BY *G.R.C.* SCALE 1"=50'
DRAWN BY *D.J.S.* IN CHARGE *R.C.A.* DATE

PROJECT NO. I-31-1(9) SHEET 44 OF 530