



PUB. NO.	STATE	FED. AID PROJECT NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
I.	VT.	I 91-1(10)		49	328

Type of Instr. Agreement	Town	Date	Book	Page	Date of Record
SA.3	Putney	8-14-74	51	31	8-29-74
TR.50					
TR.25					

STATE OF VERMONT  
DEPARTMENT OF HIGHWAYS  
INTERSTATE PROJECT in the town of  
**PUTNEY**

THE CLARKSON ENGINEERING CO., INC.  
CONSULTING ENGINEERS  
BOSTON MASSACHUSETTS

SURVEYED BY *Page* CHECKED BY *C. H. H.* SCALE 1"=50'  
DRAWN BY *J.D.* IN CHARGE *W.A.* DATE

PROJECT NO. I-91-1(10) SHEET 49 OF 328  
CONTRACT NO. 3.

STATE OF VERMONT, W.F. WHITTON  
BY Q.C.D. REC. 10/7/59 IN BK. 97 PG. 397-9  
OF PUTNEY LAND RECORD  
NOTE: SEE SHEET 49 FOR P.A.W. DEED DATA

Three Cable Guard Rail With Steel Posts  
Item No. 563  
U.S. Route #5 (Reloc.) 225 + 00 to 226 + 24 Lt.  
U.S. Route #5 (Reloc.) 225 + 00 to 226 + 24 Lt.  
225 + 00 to 226 + 24 Lt.  
225 + 00 to 226 + 24 Lt.

Property Line Fence With Steel Posts  
Item No. 541 - A  
U.S. Route #5 (Reloc.) 225 + 00 to 226 + 24 Lt.  
U.S. Route #5 (Reloc.) 225 + 00 to 226 + 24 Lt.

Removal and Disposal of Present Guard Rail  
Item No. 550  
U.S. Route #5 (Reloc.) 226 + 24 to 227 + 20 Lt.  
U.S. Route #5 (Reloc.) 226 + 24 to 227 + 20 Lt.

Paved Median Ditch  
Item No. 103  
1210 + 00 to 1210 + 25

Construct Special Ditch  
Item No. 226  
U.S. Route #5 (Reloc.) 223 + 50 to 226 + 24 Lt.  
Town Road #25 3 + 00 to 5 + 00 Lt.

Construct Drive  
Item No. 226  
226 + 50 to 226 + 50 Lt.

Excavation & Removal of Existing  
cement concrete pavement  
Item No. 120  
226 + 00 to 226 + 00 U.S. #5  
226 + 00 to 230 + 50  
Construct Approach  
226 + 00 to 230 + 50

Drilling & Blasting of Solid Rock Subgrade  
Item No. 120  
226 + 00 to 226 + 00 U.S. #5  
226 + 00 to 230 + 50  
Construct Approach  
226 + 00 to 230 + 50

DEMOLITION AND REMOVAL OF BUILDING  
Item No. 566  
1212 + 40 Lt. 1213 + 40 Lt.  
1212 + 40 Lt. 1214 + 00 Lt.  
1213 + 25 Lt. 1214 + 80 Lt.

NOTE: OWNER TO VACATE ON OR BEFORE  
NOV. 1, 1959 (STA. 1211 + 11-1216 + 22)

NOTE: CONSTRUCT EMERGENCY WATER  
SUPPLY POND AT 223 + 50 RT.  
SIZE AND LOCATION TO BE  
DETERMINED BY THE ENGINEER.

Begin Mant Agreement  
TR 25 1158 2 (17)

End Mant Agreement  
TR 25 1158 2 (17)

RESERVOIR  
PARCEL SP 65  
STATIONS 223+14-227+80 S.L.  
AREA 0.3 AC  
COND. 7/3/59  
REC. SEC. # 53

#49B HENRY H. & HAZEL E. PHELPS  
(A.O. 18) STA. 1212+07-1213+24  
COND. 7/3/59  
REC. PUTNEY BK. 35-PG. 303-7/24/59

#55E TOWN OF PUTNEY  
(A.O. 2-1) STA. 1212+48-1213+50  
COND. 7/3/59  
REC.: SEE # 53

END CONSTRUCTION  
Construct Satisfactory Approach

SURPLUS PARCEL 65  
GRANTEE: PAULA J. BARTON  
CONVEYANCE: VT. Q.C. DEED  
DATE: MARCH 15, 1966  
AREA: 0.3 ACRE

U.S. Rte. #5 Survey Curve Data  
Δ = 30° - 09' Rt.  
D = 8'

Rev. U.S. Rte #5 Relocated  
Δ = 30° - 09' Rt.  
D = 7'

R = 819.02'  
T = 220.61'  
L = 450.71'  
E = 29.19'

Bank = 15/16" per foot

