FOR FHWA OV. NO.	STATE	FED. AID PROJECT NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
1	VT.	I 91-1(11)	POST WAR	71	555

Construct Special Ditch
Item No. ~~[illegible]~~ 161-A
1234 + 00 to 1234 + 50 Lt.

Bituminous Grouted Stone Gutter
Item No. 553
~~1236 + 25 Rt.~~

Three Cable Guard Rail With Steel Post
1236 + ~~00~~ to 1242 + ~~00~~ Lt.
1236 + 20 to 1240 + 04 Rt.

GRANITE CURB
ITEM 556-B
1229 + 77 - 1236 + 23 RT.

Bituminous Concrete Curb
Item No. 555
1236 + 23 to 1239 + 50 Rt.

GRANITE SLOPE EDGING
ITEM 556A
1230 + 79 - 1235 + 21 RT

Paved Median Gutter
Item No. 361-B
1227 + 50 to 1227 + 75
1231 + 83 to 1232 + 05
1236 + 25 to 1236 + 50
1241 + 00 to 1241 + 25

Property Line Fence With Steel Posts
Item No. 583 - B
1233 + ~~12~~ - 1242 + 00 LT (828')
1226 + 00 to 1242 + 00 RT (1785')

Channel Excavation of Earth Item 106-A
Chase Brook
1 + 50 to 1 + 79
4 + 29 to ~~5 + 25~~ 6+00

Construct Special Ditch Item No. 161

~~B.M. No. 178 Elev. 568.24~~

P.O.S.T. 1231 + 04.3

P.O.S.T. 1233 + 34.8

P.O.S.T. 1235 + 15

P.O.S.T. 1236 + 75.0

P.O.C. 1238 + 00 Interstate
3 + 00 Channel Line
Skew 60° Lt. Tangent to Curve
Proposed 8'x8' Reinforced Concrete Box
for additional Details
See Sheets 180-181

~~T.B.M. Elev. 561.68~~

P.I. 1242 + 13.5
1241 + 49.5

P.C. 1227 + 29.8

Pavement Width 24'

NORTHBOUND LANE
NORTHBOUND LANE
DECELERATION LANE
NORTHBOUND LANE
NORTHBOUND LANE
ACCELERATION LANE

4' TREATED SHOULDER

12' TREATED SHOULDER

MATCH LINE

R.O.W. Fence

#56 WALTER A. RICHTER

EDWARD R. NAGEL

Meadow

Woods

Small Pine Trees

Swampy

Alders & Brush

CHASE BROOK

Hub & Nail

N 3°-08'-03" W

For Additional Details of Safety Turnout
See Sheets 78 & Roadway Standard Sheet B-17

Interstate Curve Data
Δ = 29° - 03' - 15" Rt.
D = 1°
R = 5729.65'
T = 1484.7'
L = 2905.4'
E = 189.2'
Bank = 5/16" per ft.

NOTE:
Thin out and trim trees between Station 1232 + 00 - 1236 + 50 Rt. to the R.O.W. Line.

NOTE: ERECT R.O.W. FENCE PRIOR TO COMMENCEMENT OF CONSTRUCTION.
1236 + ~~75~~ - 1237 + 00 Lt.
1236 + ~~75~~ - 1236 + 83 Rt.

ERECT R.O.W. FENCE PRIOR TO COMMENCEMENT OF CONSTRUCTION. SAID FENCE TO ALLOW ACCESS TO BOX CULVERT.
1233 + 72 - 1250 + 61 LT.

1227 + 50 Lt.
New 18" x 64' R.C.P.

1231 + 80 Med. to 1232 + 50 Lt.
New 18" x 80' R.C.P.

1231 + 80 Med. to 1231 + 80 Rt.
New 18" x 80' R.C.P.

1231 + 50 to 1231 + 50 Rt.
New 18" x 80' R.C.P.

1231 + 50 to 1231 + 50 Rt.
New 12" x 40' A.C.C.M.P.

1231 + 80 Water Pipe
3'-0" Below Old Ground

Approx. Location of Water Pipe to Richter Barn

1229 + 77
END 600' DECELERATION LANE

1236 + 25 Rt.
New 18" x 64' R.C.P.

BEGIN 1'-0" ACCELERATION LANE
1236 + 25 Rt.
New 18" x 64' R.C.P.
With 2-18" x 6' A.C.C.M.P. (Elbow)

1241 + 00 Rt.
New 18" R.C.P.
1241 + 00 LT. - 1242.08 RT.
6" PACCGM UND.

R.O.W. FENCE
1237 + 50 RT. - 1238 + 50 LT.
6" PACCGM UND.

PARCEL: 56A
GRANTOR: WALTER A. RICHTER
STATION: 1231 + 60
RIGHTS: WATER PIPE LINE
TITLE TAKEN: Q. C. D. 6/14/60
RECORDED: PUTNEY BK 36 PG 199 6/15/60

PARCEL: 57
GRANTOR: DEXTER W. & GLADYS L. KATHAN
STATIONS: 1231 + 65 - 1235 + 50 Z
TAKING: 0.5A ±
REMAINDER: 3.5A ±
RIGHTS: NONE
TITLE: W. D. 6/12/60
RECORDED: PUTNEY BK 36 PG 200 6/16/60

PARCEL: 58
GRANTOR: EDWARD R. NAGEL
STATIONS: 1231 + 96 - 1250 + 83 ±
TAKING: 14.3 A ±
REMAINDER: 54.7 A ±
RIGHTS: WATER LINE
TITLE TAKEN: STA 1242 + 45 ±
COND. 5/28/60
RECORDED: PUTNEY BK 36 PG 149-61 8/25/60

ROW FENCE

4'x4' SPRING BOX

+0.600 % Lt. & Rt.

-2.070 %

Cut to Fill Transition
1235 + 40 to 1236 + 15 Rt.

Fill to Cut Transition
1226 + 63 to 1227 + 38 Lt.

℄ Existing Brook Profile

1241 + 50 LT. 1242 + 00 RT.
GRADIENT 6" PACCGM UND

| | | |