Demolition and Removal of Building
Item No. 586
1378 + 15 Rt. #2A
1378 + 50 Lt. #2B
1384 + 10 Lt. #3C
1383 + 00 Lt. #3A
1383 + 15 Lt. #3B

Gravel Backfill
Item No. 222MOD
~~1380+00 to 1380+60 Lt~~
~~1382+00 to 1386+00 Lt~~
1381+60 to 13[illegible]

* Construct U-Turn
~~1370+46~~ 1393+50
REFER TO R'WAY STD. B-17

SUB-BASE OF SAND
Item No. 202
1380+00 to 1386+00 Lt.
1382+00 to 1386+00 Rt.

CONSTRUCT SPECIAL DITCH
ITEM # 101-A
1370+00 TO 1371+00 RT.

* Paved Median Gutter
Item No. 361-8
1374 + 25 to 1374 + 50
1374 + 75 to 1379 + 00
~~1382 + 25 to 1382 + 50~~
1385 + 33 to 1385 + 83
1382+75 to 1391+15

Plank Guard Rail With Pressure Treatment
Town Road #58
1378+75 Lt

Property Line Fence with Steel Posts
Item No. 583-8
1370 + 00 to 1386 + 00 Lt.
1370 + 00 to 1386 + 00 Rt.
1379+[illegible] Rt.

Bituminous Grouted Stone Gutter
Item No 553
1380+10 RT.
1380+50 Rt.
1385+58 to ~~1386+00 Rt.~~ 1379+90 Rt.

* Three Cable Guard Rail with Steel Posts, Item 543
1370 + 00 to 1372 + 50 Rt.
1378 + 94 to 1385 + 66 Rt.
50 70

* Bituminous Concrete Curb
Item No. 555
1379+ 00 to 1382 + 50 Rt.
8 19 34.28

* Planting Trees, Shrubs and Vines
Item 631
1373 + 00 to 1375 + 50 Left 90'
American Cranberry Bush (Viburnum Trilobum)

* STAGE II
CONSTRUCTION ITEMS

FOR NO REG. NO	STATE	FED. AID PROJECT NO	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
1	VT.	I - 91-1(17) 236	POST WAR		

S.A. #4 Curve Data
Δ = 10° - 33' Lt.
D = 4°
R = 1432.7'
T = 132.3'
L = 263.8'
E = 6.1'
Bank = 3/4" per ft.

PARCEL: 73
GRANTOR: GEORGE C. & FANNY E. WOODBURN
STATIONS: 1365+28-1379+90±
TAKING: 3.4 A± L.A.
REMAINDER: NONE
RIGHTS: NONE
TITLE TAKEN: WD 5/10/60
RECORDED: WESTMINSTER-BK. 50-PG. 23 - 5/16/60

PARCEL: 75
GRANTOR: ERNEST V. & ALICE C. HOLMES
STATIONS: 1378-97-1390+70±
TAKING: 5.8 A± L.A.
REMAINDER: 2.2 A±
RIGHTS: NONE
TITLE TAKEN: COND 5/25/60
RECORDED: WESTMINSTER-BK. 48-PG 343-59 - 5/25/60

PARCEL: 96
GRANTOR: JOSEPH A. & MYRTLE A. PARDA
STATIONS: 1365+02-1380+48±
TAKING: 5.6 A± L.A.
REMAINDER: 6.4 A±
RIGHTS: CULVERT-STA 1370+00± 1374+50±
P.L. FENCE
TITLE TAKEN: COND 5/25/60
RECORDED: WESTMINSTER-BK. 48-PG 343-59-5/25/60

PARCEL: 98 D
STATIONS: 1378+97-1388+35±
TAKING: 2.0 A± L.A.

GENERAL NOTES:
Plant American Cranberry Bush 3' apart at toe of slopes.
Deciduous Shrubs should be 2 to 3 feet in height, with not less than 4 canes, 2 feet and up.
All plant material to be graded according to American Standards for Nursery Stock.

Stage 2 Construction
17 of 189 sheets

STATE OF VERMONT
DEPARTMENT OF HIGHWAYS
INTERSTATE PROJECT in the town of WESTMINSTER
STAGE I CONSTRUCTION
THE CLARKESON ENGINEERING CO., INC.
CONSULTING ENGINEERS
BOSTON MASSACHUSETTS
SURVEYED Pogor CHECKED G.K.
DRAWN J.D. APPR. H.Mc. S.C.A.
PROJECT NO. I-91-1 (17) 236 SHEET 13 OF
CONTRACT NO. 1

3