MATCH LINE
MATCH LINE
PARCEL: 170
GRANTOR: RUTLAND RAILWAY CORP
STATIONS: 1879+25 NBL - 1879+78 SBL
RIGHTS: CROSSING EASEMENT
SLOPE - STA. 1879+23 - 1879+21 NBL RT.
2665.50 FT
meadow
brush and woods
brush and woods
150' NBL
162' NBL
215' NBL
265' NBL
365' NBL
200'
300'
woods & brush
brush
NEW CHANNEL
120'
PARCEL: 162
GRANTOR: KENNETH G. CLAYTON
STATIONS: 1873+55 - 1879+15 NBL
TAKING: 0.9 A ± L.A.
REMAINDER: 2.5 A ±
RIGHTS: SPRING - STA. 1873+85 NB RT.
PARCEL: 144C
STATIONS: 1877+15 - 1878+58 NBL
TAKING: 1.8 A ± L.A.
PT 7 - 05.6
PARCEL: 176 A,B
GRANTOR: NEW ENGLAND POWER COMPANY
STATIONS: 1879+15 - 1892+50 NB
TAKING: 7.3 AE
REMAINDER: 10.2 AE
RIGHTS: CHANNEL - STA. 1881+20 SB - 1882+26 NB
FLOWAGE - STA. 1884+00 NB - 1895+00 NB
TITLE TAKEN 6/20/61
RECORDED ROCKINGHAM BK. 113 PG 183 - 195 6/20/62
Three underground N.E.T.T. Co. cables to be lowered in place by employees or agents of N.E.T.T. Co. to positions 3.0' under proposed channel. See points A to B.
Contractor is hereby directed to contact N.E.T.T. Co. Engineering personnel regarding underground cable location. DO NOT DAMAGE.
BACKWATER
PT 1 - 65.0
303.24
49°
NEW CHANNEL LINE
CURVE DATA
Δ 49° 00' Lt.
D 8°
R 716.20
T 326.4
E 70.9
PI 4 + 18.5
3 + 79.2
-0+50
South 0.35
PC 0 - 93.1
Flow
CONTROL OF ACCESS IS COMPLETE ON THIS SHEET
Staged Construction
ROCKINGHAM
Sheet 16 of 176