



- \* THREE CABLE GUARD RAIL w/ STEEL POSTING  
ITEM 542  
3093+04-3094+88 Lt. 3097+39-3093+75 NB Rt.  
3094+37-3094+73 Lt. 3095+85-3093+93 Lt.  
3096+23-3098+36 Lt. 3095+54-3095+77 Lt.  
3096+46-3099+84 Lt. 3095+31-3099+101 Lt.
- \* Stage 2 Construction
- TOP SOIL - ITEM 621  
3092+27-3092+78 SB Lt.
- SOODING - ITEM 612  
3092+27-3092+78 SB Lt.
- DRILLING / BLASTING of SOLID ROCK  
ITEM 114  
3100+50 SB-3106+00 SB  
3100+50 NB-3104+00 NB
- \* BITUMINOUS CONCRETE CURB  
ITEM 555  
3095+50-3099+25 NB Rt.  
3092+39-3093+75 NB Rt.
- \* PAVED MEDIAN GUTTER  
3098+93-3099+25 NB Lt.  
3104+08-3104+40 NB Lt.
- TWO CABLE GUARD RAIL  
ITEM 542  
State Aid #1  
12+20-13+28 Rt.  
11+80-15+10 Lt.  
15+56-17+96 Lt.  
14+03-18+76 Lt.
- CONSTRUCT DRIVES  
STATE AID #1  
15+36 Lt.  
16+70 Rt.  
11+25 Lt.
- PROPERTY LINE FENCE w/ STEEL POSTS, ITEM 583-B  
3091+86-3093+00 NB Rt.  
3092+27-3095+30 SB Lt.  
3093+95-3104+00 NB Rt. - 3106+00  
3096+50-3103+00 SB Lt. - 3106+00
- REMOVAL OF PRESENT SUPERSTRUCTURE, ITEM 442  
13+00-5A\*1 V
- DEMOLITION & REMOVAL OF BUILDINGS, ITEM 136  
3097+42 Lt. B.  
3099+10 Lt. SB.

State Aid #1 Compound Curve

Part 1	20° 05' Rt.
Δ	4°
R	1432.4
T	252.6
L	308.0
E	22.7
B	9' 11" per ft.
Part 2	30° 45' Rt.
Δ	6°
R	954.9
T	282.5
L	572.5
E	35.1
B	3' 4" per ft.

Curve Data

Surv. & Rev. SB	Surv. & Rev. NB
Δ 48° 21' 32" Rt.	Δ 48° 21' 32" Lt.
D 3'	D 3'
Q 1909.86	Q 1909.86
T 857.51	T 857.51
L 1611.96	L 1611.96
E 103.67	E 103.67
B 13' 16" per ft.	B 13' 16" per ft.

Type of Instr. Agreement	Town	Date	Proj. Date
	Windsor	10/29/74	70/18/86



STAGE 2 CONSTRUCTION  
 WEATHERSFIELD-WINDSOR-HAMILTON  
 PROJECT - I-91-100 (8/86)  
 CONTRACT 4  
 Sheet 27 of 28/100

Control of Access is Complete on this sheet  
 within the indicated Working Areas Lines