

CONTROL OF ACCESS IS COMPLETE ON THIS SHEET.

TWO CABLE GUARD RAIL
ITEM 541
T.R. #12 STA. 6+86 TO STA. 122+00 RT.
T.R. #12 STA. 8+50 TO STA. 122+02 LT.
T.R. #12 STA. 18+50 TO STA. 222+55 LT.
T.R. #12 STA. 18+84 TO STA. 222+55 RT.

STONE FILL FOR SLOPE PROTECTION (HEAVY TYPE)
ITEM 511
M.B. STA. 6703+65 TO STA. 6703+95 LT.

WIP RAIL (HEAVY TYPE) ITEM 512
M.B. STA. 6700+20 TO STA. 6702+00 RT.
M.B. STA. 6700+00 TO STA. 6700+00 LT.

CONSTRUCT DRIVE
T.R. #12 STA. 7+60 LT.
12+50 LT.
12+50 RT.

STANDARD STEEL BEAM GUARD RAIL
W/STEEL POSTS ITEM 545-E
M.B. STA. 6700+00 TO STA. 6704+00 RT.

H. Denio
G. Lamothe

George J. & Virginia Lamothe

Henry A. & Mildred T. Denio

Henry A. & Mildred T. Denio

ALL DRIVES AS INDICATED ON
PLANS ARE SUBJECT TO PER-
MITS PURSUANT TO TITLE 19,
SECTION 143, V.S.A.

T.R. #12	
Δ	31'-32'-40"
Δ ₀	12'-03'-44"
R	475.00'
T	229.34
L	427.32
E	92.47
BANK	3/4" FT. RT.

T.R. #12 IS TO BE BUILT IN ITS ENTIRETY
DURING STAGE 1 CONSTRUCTION.
H. Denio
G. Lamothe
NOTE: FOR R & G TIES SEE TIE SHEET NO. 24 & 25

STATE OF VERMONT
DEPARTMENT OF HIGHWAYS

TOWN OF BARRETT - ST. JOHNSBURY
ROUTE NO. 121
T.R. #12 STA. 19+00 TO STA. 21+50 RT.
CONTRACT # 2
STAGE CONSTRUCTION
PROJECT NO. 121
SHEET 55 OF 57

ALUMINUM CONCRETE CURB ITEM 555
M.B. STA. 6701+50 TO STA. 6712+50 LT.

BEGIN RELINQUISHMENT NO. X
T.R. 12 5+00 & LENGTH 2707'

JUTE MATTING ITEM 623
T.R. 12 STA. 19+50 TO STA. 21+50 RT.

PLAN SCALE
1" = 40 FEET

NOTES - STAGE 2 ITEMS
CLARKSON, CLOUGH AND SOREL
CORPORATION ENGINEERS
ALBANY, NEW YORK