



CONTROL OF ACCESS IS COMPLETE ON THIS SHEET

TBM 197  
US ELEV  
633.11

TREATED TIMBER CURB  
ITEM 616.35  
S.R. 919+50 TO 926+00 LT.  
N.B. 917+30 TO 929+00 RT.

SOUTH BOUND

Δ 5'-54"-59"  
Dc 0'-15"-00"  
R 22,918.31  
T 1184.25  
L 2366.40  
E 30.58  
BANK 0217H LT.

NORTH BOUND

Δ 19'-00"-00"  
Dc 6'-45"-00"  
R 7639.44  
T 1278.40  
L 2533.33  
E 106.23  
BANK 0297H LT.

DRILLING AND BLASTING OF SOLID ROCK  
SUBGRADE, ITEM 206.10  
N.B. STA. 929+00 TO 931+00

VT. GRID

JUTE MATTING ITEM 654.10  
N.B. STA. 923+00 - STA. 925+00 LT.  
N.B. STA. 920+60 - STA. 920+00 RT.  
S.B. STA. 916+00 - STA. 923+23-LT.  
N.B. STA. 911+80 - STA. 921+30 LT.  
S.B. 915+00 - 916+30 LT.

MATCH SHEET 64

MATCH SHEET 69

N.B. 916+24.01  
Cut Existing 12" Water Line of  
Ditch to Drive Outlet  
150' Lt. as Item 204.20

N.B. Sta. 917.00 L.L. & R.  
New 24" A.C. Pipe (12' x 12')  
W/ 2" x 2" Strainers  
W/ 12" x 12" Catch Basin  
150' Lt. as Item 204.20

N.B. Sta. 917.00 L.L. & R.  
New 24" A.C. Pipe (12' x 12')  
W/ 2" x 2" Strainers  
W/ 12" x 12" Catch Basin  
150' Lt. as Item 204.20

N.B. Sta. 917.00 L.L. & R.  
New 24" A.C. Pipe (12' x 12')  
W/ 2" x 2" Strainers  
W/ 12" x 12" Catch Basin  
150' Lt. as Item 204.20

N.B. Sta. 917.00 L.L. & R.  
New 24" A.C. Pipe (12' x 12')  
W/ 2" x 2" Strainers  
W/ 12" x 12" Catch Basin  
150' Lt. as Item 204.20

N.B. 918+50  
160' Rt.

N.B. 917+30  
103' Rt.

N.B. 916+00 LT.  
CONC. DAM  
BROKEN CONC. DAM.

N.B. 916+00 LT.  
CONC. DAM  
BROKEN CONC. DAM.

N.B. 916+00 LT.  
CONC. DAM  
BROKEN CONC. DAM.

N.B. 916+00 LT.  
CONC. DAM  
BROKEN CONC. DAM.

N.B. 916+00 LT.  
CONC. DAM  
BROKEN CONC. DAM.

\*THREE CABLE GUARD RAIL W/LIGHT STEEL POSTS  
ITEM 621.21

N.B. STA. 916+00 TO STA. 924+08 RT.  
N.B. STA. 918+94 TO STA. 924+06 LT.  
S.B. STA. 915+40 TO STA. 922+30 RT.  
S.B. STA. 918+78 TO STA. 921+55 LT.

EXCELSIOR MATTING, ITEM 654.15  
NB 916+00-917+00 LT  
SB 924+25-927+00 LT  
SB 929+50-930+20 LT

STONE FILL, TYPE II, ITEM 613.13  
NB 921+10 TO 921+41 RT

DEMOLITION & DISPOSAL  
OF BUILDING ITEM 202.10  
NB 919+53 RT. CONC. RESERVOIR

CONSTRUCT U-TURN  
SB 928+50 RT - NB 929+50 LT

STONE FILL TYPE II ITEM 613.11  
SB 922+28 TO 922+54 RT  
SB 923+03 TO 923+32 LT  
NB 920+00 TO 921+10 RT  
NB 921+41 TO 921+71 RT  
NB 922+31 TO 922+71 LT  
NB 922+71 TO 922+98 LT

PLAN SCALE  
0 50 100  
100 FEET

CHAIN LINK FENCE (6' HIGH)  
ITEM 620.11  
NB 926+40 - 931+00 RT

WOVEN WIRE FENCE WITH STEEL POSTS  
ITEM 620.23  
N.B. STA. 916+00 TO STA. 931+00 RT.  
S.B. STA. 915+40 TO STA. 930+20 LT.

\* DENOTES STAGE 2 ITEMS  
CLAWKESON, CLOUGH AND YOKEL  
ALBANY CONSULTING ENGINEERS NEW YORK

NOTE FOR DETAILS SEE THE SHEETS NO. 29 & 30

STATE OF VERMONT  
DEPARTMENT OF HIGHWAYS

TOWN OF ST. JOHNSBURY

ROUTE No. 1-91 STA

SOUTHBOUND 915+40 TO 930+20

NORTHBOUND 916+00 TO 931+00

STAGE CONSTRUCTION II

PROJECT NO. 1-91-3 (17)

SHEET 46 OF

DESIGNED BY: C.C.K.  
DRAWN BY: J.W.  
CHECKED BY: J.W.  
DATE: 10/1/54  
COMPLETED: J.W.