

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
9	VI.	688	1927	23	80

WOOD GUARD RAIL REQUIRED
 RIGHT
 STA. 285+88 to 286+12 LENGTH 24 FT.
 LEFT
 STA. 278+00 to 278+24 LENGTH 24 FT.

CABLE GUARD RAIL REQUIRED
 RIGHT
 STA. 278+00 to 283+00 LENGTH 500 FT.
 LEFT
 STA. 280+60 to 281+32 LENGTH 72 FT.
 STA. 284+30 to 287+26 " 296 "

NEW CULVERTS REQUIRED

STA. 278+12 18" REINF CONG PIPE LENGTH 40 FT.
 CONG. CLASS A (1-2-4) 1.9 CU YDS.
 REINF STEEL 60 LBS.
 STA. 280+78 2x2 Box
 CONG. CLASS A (1-2-4) 14.3 CU YDS.
 REINF STEEL 342 LBS.
 STA. 285+00 15" REINF CONCRETE PIPE LENGTH 32 FT. - WITH DROP INLET
 CONG. CLASS A (1-2-4) 10.0 CU YDS - CLASS B (1-2-5) 11 CU YDS.
 REINF STEEL 103 LBS.
 STA. 285+15 CORR METAL PIPE 12" LENGTH 20 FT. - LE FT.
 CONG. CLASS B (1-2-5) 15 CU YDS.
 REINF STEEL 33 LBS.

PLAN	REVISIONS	DATE	BY	CHKD
1	AS Dwg			
2	AS Dwg			
3	AS Dwg			
4	AS Dwg			
5	AS Dwg			

PROFILE	REVISIONS	DATE	BY	CHKD
1	AS Dwg			
2	AS Dwg			
3	AS Dwg			
4	AS Dwg			
5	AS Dwg			

