POOR ORIGINAL COPY

R.F-F028-1(1)

I.R.-M 1932

IF ORDERED BY THE ENGINEER THE PRESENT MACADAM SURFACE 185+00 TO 186+00 WILL BE REWORKED AND SUB-BASE & NEW SURFACE ADDED TO INSURE A SATISFACTORY CONNECTION OF OLD & NEW WORK

STATION 185+00
BEGINNING OF PROJECT
END OF BITUMINOUS SURFACE CONSTRUCTED IN 1931

~NOTE~
A 6" Sub-base of Stone is required the entire length of the Project.

Curve #1
Δ- 3°46' Rt.
D- 2°
R- 2866.9
T- 94.2
L- 188.3
E- 1.5

Curve #2
Δ- 1°36' Rt.
D- 0°30'
R- 11459.2
T- 160.0
L- 320.0
E- 1.0

BURLINGTON

MARY PHELPS

W. H. KELLER

DAVID DICHARME

CHAS. DEWYER

N. STANFORD

PASTURE

MEADOW

WELL

STR. 187+00 - 188+00 USE FLAT SLOPES

STR. 194+00 - 195+00 USE FLAT SLOPES

1.80

185+00 - 186+00
10" Slag Stone Base

186+08 - 193+00
6" Slag Stone Base

193+00 - 197+00
10" Slag Stone Base

B.M. = Bl. SPIKE IN ROOT 14" MAPLE 22.3 FT. STA. 187+30 ELEV. 79.88

Series S No. 128-M
Sheet 40 of 50

2