



NOTE
 STA 398+63.5 to STA 463+09.8
 ALL NECESSARY EXCAVATION THAT IS MADE UNDER THE PAVEMENT IS TO BE USED AS FILL MATERIAL UNDER THE SLAB. ALL ADDITIONAL MATERIAL THAT MAY BE REQUIRED AS A SHARPE COURSE TO BRING THE SUB GRADE UNDER THE PAVEMENT TO FINISHED SUB GRADE SHALL BE OF GRAVEL AND PAID FOR AS SUB BASE OF GRAVEL.

NOTE
 THE QUANTITIES OF BORROW AS GIVEN ON THE EARTH WORK SHEETS ARE ONLY APPROXIMATE. THE INTENT OF THE PLANS IS THAT THE CONTRACTOR IS TO CONSTRUCT SUCH SIDEFILLS AND SHOULDERS AS ARE NECESSARY TO HOLD FORMS AND PAVEMENT. THE CONTRACTOR IS EXPECTED TO COMPACT SIDE FILL AND SHOULDERS BETWEEN STA 388+25 AND STA 393+50. THE STONE FILL, SHOULDERS AND SUCH OTHER FILL NECESSARY TO COMPLETE THE ROADWAY AS SHOWN ON THE SECTIONS ARE TO BE CONSTRUCTED BY STATE FORCE ACCOUNT.