

GUARD RAIL REQUIRED
ON LEFT
 Sta 137+00 to 137+52 Length 24ft
 Sta 139+83 to 140+07 Length 24ft
 - 196+65 - 196+89 = 24'
 - 199+55 - 199+79 = 24'
ON RIGHT
 Sta 135+00 to 140+12 Length 512ft
 - 196+65 - 196+89 = 24'
 - 199+55 - 199+79 = 24'
TOTAL THIS SHEET 658ft

NEW CULVERTS REQUIRED
 Sta 137+90 2'-12" Reinforced concrete
 1-2-4 concrete 40 cu yds
 1-3-6 " " 6.8 "
 Reinforcing steel 69 lbs
 Sta 139+95 18" Cor Iron Pipe 28ft
 1-2-4 concrete 1.5 cu yds
 Sta 196+77 18" Cor Iron Pipe 30ft
 1-2-4 concrete 1.5 cu yds

CULVERT REPAIRS REQUIRED
 Sta 149+67 1-2-4 concrete 1.0 cu yds
RELAYING PIPE CULVERTS
 Sta 149+67 12" Cor Iron Pipe 28ft
STONE BASE REQUIRED
 Sta 149+67 to 150+00 Length 33ft

FEEDING	STATE	FEED AROUND	FEED YEAR	SHEET NO	TOTAL SHEETS
0	VT	27	1920-21	10	75

10/21/00
 E.P. HOSCH
 M.A. CHASE
 P.E. CIVIL ENGINEER

10/21/00
 E.P. HOSCH
 M.A. CHASE
 P.E. CIVIL ENGINEER

