

WOOD GUARD RAIL REQUIRED

STA 120+3 - 20+6	LENGTH 24 FT.	STA 120+43 - 120+67	LENGTH 24 FT.
STA 132+00 - 133+12	LENGTH 24 FT.	STA 129+40 - 129+04	LENGTH 36 FT.
(LEFT)	TOTAL - 72 FT.	STA 132+40 - 133+20	LENGTH 30 FT.
		(RIGHT)	TOTAL - 160 FT.

NEW CULVERT REQUIRED

STA 120+59 - 15" REINFORCED CONCRETE OR CAST IRON PIPE CULVERT - LENGTH 20 FT.	2.1 Cu.Yds.
CONCRETE CLASS B (1-2 1/2-5)	REINFORCING STEEL 33 Lbs.
STA 133+00 - 15" REINFORCED CONCRETE OR CAST IRON PIPE CULVERT - LENGTH 20 FT.	2.1 Cu.Yds.
CONCRETE CLASS B (1-2 1/2-5)	REINFORCING STEEL 33 Lbs.

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
1	VT.	55A	1927	11	58

