

WOODEN GUARD RAIL REQUIRED
ON LEFT
 Sta. 243+26 to Sta. 243+50 Length 24'
 " 243+70 " " 247+30 " 160'
 " 251+40 " " 252+36 " 96'
 " 256+03 " " 256+27 " 24'
ON RIGHT
 Sta. 243+26 to Sta. 243+50 Length 24'
 " 244+42 " " 248+10 " 368'
 " 248+76 " " 252+36 " 360'
 " 256+03 " " 256+27 " 24'
TOTAL THIS SHEET 1080 FT

SUB-BASE REQUIRED
 Sta. 253+00 to Sta. 257+00 length 200 FT.

NEW CULVERTS REQUIRED
 Sta. 243+38 16" Cor. Iron Pipe Length 30'
 1-2 1/2-5 Concrete 18 Cu Yds.
 " 245+82 18" Cor. Iron Pipe Length 44'
 1-2 1/2-5 Concrete 25 Cu Yds.
 Sta. 251+52 2 1/2' Reinforced Concrete Box
 1-2-4 Concrete 32 cu yd.
 1-2-5 Concrete 6.41 "
 Reinforcing Steel 140 lbs
 Sta. 256+15 2 1/2' Concrete Box Reinforced
 1-2-4 Concrete 31 cu yd.
 1-2-5 Concrete 8.3 "
 Reinforcing Steel 140 lb.

