



Sta 658+00
Beginning of Project

4 BETULA Papyrifera 8'-10'
(Canoe Birch)

PASTURELAND
(Scattered Pine, Spruce & Poplar)

RAW CUT SLOPE - GRAVEL
Slope to be Graded; Strip-Saddled
between sta 676+50 & sta 679+50;
Topsoiled; Fertilized & Seeded (Formula R).
Notes: Topsoil between sta 672+00 - sta 676+50
and between sta 679+50 - sta 680+50
to be salvaged during grading
operations.

RAW CUT SLOPE - STONEY GRAVEL
Slope to be Graded; Strip-Saddled
between sta 681+25 & sta 683+50;
Topsoiled; Fertilized and Seeded
(Formula R)

STA 685+70 - STA 687+25
RAW CUT SLOPE - GRAVEL
Slope to be Graded; Strip-Saddled;
Topsoiled; Fertilized and Seeded
(Formula R).

3 BETULA Papyrifera
8'-10' (Canoe Birch)

Sta 687+25 - Sta 688+00
GRAVEL PIT
To be Graded; Topsoiled;
Fertilized & Seeded (Formula B)
Note: Topsoil to be salvaged from
grading operations.

ESTIMATED QUANTITIES

Surveyed by A.W. Coleman
Designed by A.J. Runnels
Drawn by A.W. Coleman
Traced by L.N. Brock
Checked by _____
Series F.R.P. No. 86C(2) Cont. 3111
Sheet (4) of 18 Sheets