



PARTIALLY VEGETATED CUT SLOPE - GRAVEL
 Slope graded, strip-sodded, topsoiled, and seeded (Formula B).
 Note: Grading operations to be conducted so as to preserve existing growth. Strip sodding to be done where considered necessary.

Sta 721+50 - Sta 727+00 R+
RAW CUT SLOPE - SAND
 Slope to be graded and planted with Beach Grass 12" x 1/2".

Notes: Beach grass to be transplanted from Lyndon State Forest. Grading to consist of cutting back overhang.

Sta 727+00 to 728+19 R+
RAW CUT SLOPE - GRAVEL
 Slope to be graded, top-soiled, and seeded (Formula B).

STA 730+00
 END OF PROJECT

(revised)
 Curve No. 27
 Δ 25° 20'
 D 5'
 R 1146.0
 T 257.6
 L 506.7
 E 28.6

728+42.8+
 729+14.7
 Equation - 2.2

ESTIMATED QUANTITIES

--	--

Surveyed by
 Designed by *A.J. Runnals*
 Drawn by *R.E.* Road Engineer
 Traced by *R.E.*
 Checked by
 Series FAP No. 86-C(2) Landscaping
 Sheet 6 of 15 Sheets