



NOTE
Where Box Culverts are to be extended extensions are to be dowelled to existing structure with 3/4" x 4/8" bolts spaced 4' on center. These dowels to extend into existing structure a minimum of 12" drilling, placing & grouting to be included in bid price for reworking steel.

This note applies to box culverts where extensions are necessary - Stations 1129+53, 1145+22, 1151+16, 1170+12, 1180+55, 991+00, 1005+00

