

GUARD RAIL REQUIRED ON LEFT

Sta. 32+60 to Sta. 32+84 Length 24 ft.
 - 36+51 - 36+75 - 24 -
 - 40+05 - 40+29 - 24 -
 - 44+46 - 44+70 - 24 -

ON RIGHT

Sta. 32+50 to Sta. 33+46 Length 96 ft.
 - 35+60 - 37+60 - 200 -
 - 39+60 - 41+64 - 224 -
 - 44+44 - 45+00 - 56 -

TOTAL THIS SHEET 672 ft.

NEW CULVERTS REQUIRED

Sta. 32+72 2' x 2' Concrete culvert 28 ft.
 1-2-# Concrete 5.3 cu yds.
 1-3-# Concrete 7.1 cu yds.
 Sta. 36+82 2' x 2' Concrete culvert 28 ft.
 1-2-# Concrete 5.7 cu yds.
 1-3-# Concrete 7.5 -
 Sta. 40+17 15" Cast Iron Pipe 28 ft.
 1-2-# Concrete Handrails 1.5 cu yds.
 Sta. 44+58 2' x 2' Concrete culvert 28 ft.
 1-2-# Concrete 5.3 cu yds.
 1-3-# Concrete 7.1 cu yds.

STANDARD UNDERDRAIN REQUIRED

Sta. 31+00 to Sta. 32+75 Length 175 ft.

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
9	VT.	13	1920	5	19

E. P. Welch
S. H. White

E. P. Welch
S. H. White

