



The contractor to be required to remove the logs to the neat lines as shown on the plans from Sta. 688+50.1 to Sta. 696+00.1 and use this rock in the item of Stone Fill, Item 69. Any earth excavation that is removed in this work shall be paid for under the item of Common Excavation including Bottom, Item 10-11, and used in the embankments on the project. Any trees removed shall be paid for either under Item 10-11 or under Item 109 in accordance with the specifications and special provisions. All rock thus removed will be paid for only under the item of Stone Fill, Item 69.

The contractor will be required to move and reset the two monuments on the right of Sta. 691+50.1 in accordance with the provision as set up in the note on the plans.

The contractor will be required to complete the excavation between the stations noted above to the neat lines but will not be required to place any sub-base. Any damage that he may do to the present road on account of the necessary construction operations shall be required at the contractor's own expense. Est. Rock 3900 Cu Yd.

See Sheets 14 & 14 A Plan & Profile
 65 - 76 Cross Sections

BM #6 SPIKE IN ROOT OF 24" THIN PINE 50 FT RT OF STA 723+37 ELEV 376.55
 BM #7 SPIKE IN ROOT OF 15" OAK 47 FT RT OF STA 729+22 ELEV 391.41
 BM #8 SPIKE IN ROOT OF 12" ELM 20 FT LT OF STA 728+13 (SPUR LINE) ELEV 355.26
 BM #9 SPIKE IN ROOT OF 15" ELM 35.5 FT LT OF STA 731+76 ELEV 356.36