



Sta. 56+00±-62+00±
 Sod and topsoil, to a depth of six (6) inches, within the limits of construction is to be stripped and stockpiled. This topsoil is to be used on the completed fill slopes between the bridge and end of project as shown on the plans or as directed by the engineer. This work to be paid for under item of topsoil, Item 106. The estimated yardage to be removed is 300 Cu. Yd.

PARCEL	INSTRUMENT	DATE	GRANTOR	GRANTEE	RECORDED	REMARKS
A	W.D.	6-17-38	WILLIAM J. & FRANCIS H. BRYANT	ST. OF VT.	BOOK 96 PAGE 62-38	
A-B	W.D.	3-22-40	B.W.R. & GERTRUDE KIERSTEAD	ST. OF VT.	46 329 3-27-40	

ESTIMATED QUANTITIES		SPRINGFIELD Surveyed by Designed by Drawn by Traced by Checked by Series F.P.P. No. 1354 (1) Filed Sheet 8 of 75 Sheets