

GUARD RAIL REQUIRED
 ON LEFT
 Sta 31+20 To Sta 31+80 length 60 ft
 ON RIGHT
 Sta 31+20 To Sta 31+80 length 60 ft
 TOTAL THIS SHEET 120 ft

NEW CULVERTS REQUIRED
 Sta 31+30 2 x 2' Concrete Box Reinforced
 1-2' Concrete 44 cu yds Earth Excav 41 Cu Yds.
 1-2' 5" Reinforcing Steel 800 lbs
 Sta 31+80 15' Concrete Pipe length 30 ft
 1-15' 5" Concrete 15 Cu Yds

SUB BASE REQUIRED
 Sta 41+00 To Sta 41+50 length 50 ft

DATE: 10/15/19
 DRAWN BY: [Signature]

PLAN

DATE	
BY	
CHECKED	
APPROVED	

NOTE: BOOK, QUANTITY CHECKED, SET OF DRAWINGS

PROFILE

DATE	
BY	
CHECKED	
APPROVED	

NOTE: BOOK, QUANTITY CHECKED, SET OF DRAWINGS

