

WOOD GUARD RAIL REQUIRED		CABLE GUARD RAIL REQUIRED		NEW CULVERTS REQUIRED	
OR RIGHT		OR LEFT			
Sta 361+00 to Sta 361+23 Length 23 ft.		Sta 360+80 to Sta 365+52 Length 472 ft.		Sta 361+17	24" Cast Iron Pipe Culvert 32 ft.
363+72	24"	365+13	388"		Class A Concrete (1-2-4) 26 Cu Yds
368+13	24"			Sta 362+84	Reinforcing Steel 54 pounds
370+30	24"				24" Cast Iron Pipe Cul 24 ft.
371+73	7"				Concrete Class A (1-2-4) 24 Cu Yds
					Reinforcing Steel 54 pounds
				Sta 368+20	24" Cast Iron Pipe Cul 32 ft.
					Concrete Class A (1-2-4) 26 Cu Yds
					Reinforcing Steel 54 pounds
				Sta 370+42	36" Rein. Conc. Box Cul.
					Concrete Class A (1-2-4) 150 Cu Yds
					Reinforcing Steel 969 pounds

