GUARD RAIL REQUIRED
ON LEFT
Sta 437+07 to 437+31 length 24 lin. ft.
" 441+53 to 441+77 " 24 " "
ON RIGHT
Sta 437+07 to 437+31 length 24 lin. ft.
" 441+53 " 441+77 " 24 " "

Sta 437+19 Replace 15" Corr. Iron Pipe with 18" Reinforced Concrete Pipe See Series 5A2

NEW CULVERTS REQUIRED
STA. 437+19 18" Reinforced concrete pipe Length 32 FT.
1-22-5 Concrete 2.3 cu.yd.
STA. 441+65 18" Reinforced concrete pipe Length 32 FT.
1-22-5 Concrete 2.3 cu.yd.

Sta. 441+65 Old Culvert Replaced with 18" Reinforced Pipe Line See Series 5A2

6" SUB-BASE
Sta. 438+00 to 445+50 Length 750'
9" for Bit. Macadam

16