

**WOOD GUARD RAIL REQUIRED**

ON LEFT			
Sta. 504+02 to Sta. 504+26	Length	24 ft	
" 508+41 " " 508+65	"	24 "	
" 512+63 " " 512+87	"	24 "	
ON RIGHT			
Sta. 504+02 to Sta. 504+26	Length	24 ft	
" 508+41 " " 508+65	"	24 "	
" 512+63 " " 512+87	"	24 "	
<b>TOTAL THIS SHEET</b>		<b>144 ft</b>	

**NEW CULVERTS REQUIRED**

Sta. 504+14 18" Conc. or Cast Iron Pipe	36 ft
Class "B" Concrete (1-2 1/2-5)	2.4 Cu yds.
Reinf. Steel	30 lbs
Sta. 508+52 18" Conc. or Cast Iron Pipe	32 ft
Class "B" Concrete (1-2 1/2-5)	2.7 Cu yds.
Reinf. Steel	33 lbs
Sta. 512+74 24" Conc. Box Extended 2' on Each End	3.5 Cu yds.
Class "A" Concrete (1-2-4)	3.5 Cu yds.
Reinf. Steel	209 lbs.

**6" SUBBASE**  
Sta. 500+00 to Sta. 512+00 Length 1200 ft.

**9" SUBBASE**  
Sta. 512+00 to Sta. 514+00 Length 200 ft.

