

**GUARD RAIL REQUIRED**  
**ON LEFT**  
 Sta 279+95 to 280+15 Length 24 ft.  
 283+60 - 283+84 24 "  
 285+62 - 286+02 40 "  
**ON RIGHT**  
 Sta 279+89 to 280+13 Length 24 ft.  
 283+60 - 283+84 24 "  
 285+70 - 285+94 24 "  
**TOTAL THIS SHEET 160 ft.**

**NEW CULVERTS REQUIRED**  
 Sta. 280+05 12" Con.I.P. 30 ft.  
 1-2 1/2 Concrete 1.0 cu yds.  
 Sta. 285+82 12" Con.I.P. 34 ft.  
 1-2 1/2 Concrete 1.0 cu yds.

**RELAYING PIPE CULVERTS**  
 Sta 283+72 16" Con.I.P. Tube 22 ft.  
 Relaid from Sta. 284+71  
**CULVERT REPAIRS REQUIRED**  
 Sta 283+72 16" Con.I.P. Extend 8 ft.  
 1-2 1/2 Concrete 1.5 cu yds.

**SUB BASE REQUIRED**  
 Sta 276+00 to 280+00 Length 400 ft.

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
9	VT	SR	(22)	21

