

CONSTRUCT DRIVES
 RA
 186+33.4
 189+22.7 to Cemetery
 191+36.5
 194+60.5
 195+50.5
 197+86.10

FERTILIZER & SEEDING (URBAN AREA & LAWNS)
 187+00 LL - 188+28 LL
 188+30 LL - 189+11 LL
 189+31 LL - 191+35 LL
 191+42 LL - 191+78 LL
 191+78 LL - 194+34 LL
 194+66 LL - 195+42 LL
 195+58 LL - 196+96 LL

TOP SOIL (URBAN AREA & LAWNS)
 187+00 LL - 188+28 LL
 188+30 LL - 189+11 LL
 189+31 LL - 191+35 LL (Includes Area of Sidewalk Removal)
 191+42 LL - 191+78 LL (Includes Area of Sidewalk Removal)
 191+78 LL - 194+34 LL (Includes Area of Sidewalk Removal)
 194+66 LL - 195+42 LL
 195+58 LL - 196+96 LL

STEEL GUIDE POSTS
 191+51 RA TO 196+79 RA
 RA
 193+81 (DULK)

THREE CABLE GUARD RAIL WITHOUT STEEL POSTS
 192+95 RA TO 194+39 RA
 RA

PROPERTY LINE FENCE
 ITEM 533-LL
 187+00 - 192+44 CR.

REMOVAL & DISPOSAL OF PRESENT GUARD RAIL
 192+85 LL - 193+12 LL
 193+00 RA - 194+10 RA

EXCAVATION & REMOVAL OF ROAD SURFACES & OR PAVEMENTS
 187+00 LL - 188+22 LL
 188+35 LL - 189+10 LL
 189+30 LL - 191+30 LL
 191+45 LL - 193+00 LL

CURB
 187+00 LL - 188+29 LL
 188+40 LL - 189+11 LL
 189+31 LL - 191+30 LL
 191+42 LL - 194+59 LL
 194+66 LL - 195+42 LL
 195+58 LL - 196+96 LL

ONE COURSE 5" CEMENT CONCRETE SIDEWALK
 187+00 LL TO 189+11 LL
 189+31 LL TO 196+96 LL
 191+78 LL (Walk to house)

MUCK EXCAVATION
 192+80 TO 194+25

CONSTRUCTION NOTES:
 From Sta. 187+00 LL to 195+40 LL, the Area from Dutch LL to Near Edge of Lawns (Maximum Distance of 135' LL) is to be Graded and Reshaped With Borrow, 10% 104, 2" Topsoil, and Fertilizer and Grass Seed, As Directed By The Engineer.
 Present Sidewalk of Sta. 189+35 LL to Sta. 196+96 LL is to be Removed Under Common Excavation - Item 103-A1

BM #20
 SLR 24' E
 U.S. ELEV.
 504320

STA. 195+00.0
 END PROJECT S-0163(A)
 Construct Satisfactory Approach to Sta. 197+25.0

RUTLAND PROCTOR
 Project S-0163(A)
 Surveyed By Spaulding 6/62
 Plotted By E.F. Lane 8/62
 Traced By E.F. Lane 1/63
 Sheet 46 of 143 Sheets

