



BM 30 - SPIKE IN ROOF OF 24' ELM  
16' LT. Sta. 181+14  
ELEV. 139.46

Culv. Sta 185+16

MEADOW



Sta 185+85 - Sta. 187+10 RT.  
CONSTRUCT CONCRETE CRIBBING  
(Item 71 - modified)  
For details of design and const. see  
Spec. sheets 2, 8, 10.  
Barr. ditch to be constructed along top  
of slope to prevent washing.

SLOPE TO BE SODDED (Item 102)  
3" TOPSOIL (Item 106)  
(To prevent erosion)  
When slope is rough graded, place a minimum of  
excavation over the entire exposed clay slope 12'  
before spreading top soil.  
(See sheet 2)

SLOPE TO BE SEEDDED (Item 101)  
(To erase construction scar)  
Existing shrubs to be saved.

J.F. BENTLY

BM 32 - Spike in back  
side of Pine 14' Lt. of  
Sta. 197+73  
ELEV. 166.90

Tillage

Barra

Tillage

Scar

BM 33 - Spike in roof  
of Pine 25' RT. of Sta. 203+57  
ELEV. 162.73

SLOPE TO BE SEEDDED (Item 101)  
(To erase construction scar)  
Pine Woods

Sta 203+30 - 211+00  
CLEARING & TRIMMING ROADSIDE (Item 100)  
(Clear vegetation back from top of slope to allow rounding)

Sta. 213+00 - Sta. 215+00 LT.  
Widen shoulder for parking purposes  
with such selected excess excavation  
as may be available at project.

Pine Woods

SLOPE TO BE SEEDDED (Item 101)  
SEED FORMULA B  
(To erase construction scar)

J. CANFIELD

SLOPE TO BE SEEDDED (Item 101)  
SEED FORMULA B  
(To erase construction scar)

Sta. 222+75 - Sta. 224+75 LT.  
Widen shoulder for parking purposes  
with such selected excess excavation  
as may be available at project.

Pine Woods

BM 37 - Spike in trunk  
of 8" Oak, 37' LT. Sta. 221+95  
ELEV. 150.70

SLOPE TO BE SEEDDED (Item 101)  
3" TOPSOIL (Item 106)  
(To erase construction scar)

Pine, Birch & Elm

SLOPE TO BE SEEDDED (Item 101)  
(To erase construction scar)

BM 36 - Spike in roof  
of 16" Pine 25' RT. Sta. 218+18  
ELEV. 158.63

SLOPE TO BE SEEDDED (Item 101)  
3" TOPSOIL (Item 106)  
(To erase construction scar)

Pine, Birch & Elm

SLOPE TO BE SODDED (Item 102)  
(To erase construction scar)