

Mrs BERTHA WALKER

D 4°

R 1432.7

T 371.2

L 726.3

E 47.4

Bank 1/2" per ft.

Sta. 426+23
12" crossed Timber
Curb ITEM 98

Sta. 427+00
12" C.G.M.P.A.C.
Metal. D.I. With
6' long grate See Sheet -

Sta. 428+98
Begin crossed Timber Curb ITEM 98

Sta. 430+50
End crossed Timber Curb

REV. STA. 431+06.57
SUR. STA. 431+00 E.I. + 6'

REV. PT. 429+79.5

426+50±
Construct drive
to field

427

428

429

430

431

5 55° 24' W

75'

190.0

175'

25'

Gate

6' M
Save

Field

427+20 Rt
Begin Tree Planting

POST. 428+30.9 =
Orig. Pl. 428+30.8

Tillage

Note:

Area = 0.64 acre

38.75 36.95 39.37

7+00± Rt
Approach to Field

TREE PLANTING Item 107

Native growth White Spruce (*Picea Alba*) - No Limbing permitted

1st Row - 75 ft from E - Trees 5' to 8' high spaced 8' c. c.

2nd Row - 6 ft. back of 1st Row - Trees 6' to 10' high spaced 8' c. c.

3rd Row - 6 ft. back of 2nd Row - Trees 6' to 10' high, spaced 8' c. c.

Trees to be staggered in rows to provide maximum closure.

Time of year in which trees are to be set out shall be

determined by the Engineer

(Estimated No. of Trees 175)