



CONSTRUCT DRIVE  
 27+17 Df (Fairview Terrace)  
 28+29 Df (Fairview Terrace)  
 5" CEMENT CONCRETE SIDEWALK  
 ITEM 560  
 82+22 - 86+00 Df  
 Fairview Terrace 26+89 - 29+30 Df  
 1/4" + 15" - 13" + 20" Rf  
 DEMOLITION & DISPOSAL OF BUILDING  
 ITEM 556  
 81+15 Df  
 82+25 Df  
 5" Conc. concrete curb, sidewalk  
 81+15 - 82+25 Df

VERTICAL GRANITE CURB, ITEM 556-B  
 82+50 - 86+00 Df  
 82+22 - 86+00 Df  
 MEDIAN  
 81+30 - 86+00'

CUTTING & REMOVING TREES, ITEM 102  
 84+65 Df  
 85+34 Df  
 87+21 Df

THREE CABLE GUARD RAIL  
 ITEM 542  
 Fairview Terrace  
 26+00 - 28+24 Df

REMOVAL & DISPOSAL OF PRESENT  
 GUARD RAIL, ITEM 549  
 Fairview Terrace  
 26+25 - 28+75 Df

REMOVAL OF RETAINING WALL  
 ITEM 103-B  
 85+15 - 85+75 Df  
 REMOVE DROP INLETS, ITEM 103-B  
 85+55 Df  
 85+70 Df  
 85+76 Df

REMOVAL OF BIT. CONC. CURB, IT. 557  
 REM. & RESET OF THREE CABLE GUARD RAIL, IT. 548-B  
 82+50 - 86+00 Df  
 REMOV. & RESET OF CURB, IT. 557  
 REMOV. & RESET CONC. SIDEWALK, IT. 561  
 81+00 - 82+22 Df  
 82+22 - 86+00 Df  
 81+44 - 82+76 Df

81+00  
 BEGIN APPROACH  
 F-041-2(5)

PI 01+10.65  
 81+10.34

Airport Dr.  
 POT 27+00.0

Green Mt. Studio Corp  
 81+30 - 82+10 Df  
 New 18" x 18" RCP  
 81+30 - 82+10 Df  
 81+30 - 82+10 Df  
 81+30 - 82+10 Df

#42  
 2 1/2 s.f. ho.  
 HUGH COLLINS  
 27+70 Df (Fairview Terrace)  
 28+45 Fairview Terrace  
 END CONSTRUCTION

HERBERT MILLER  
 #40  
 2 1/2 s.f. ho.

PLAN SCALE  
 1" = 40'

HARTFORD  
 SURVEYED BY: Sevick DATE: 9/6  
 DRAWN BY: Geo DATE: 10/6  
 TRACED BY: BEW DATE: 10/6  
 PROJ. F. NO. 041-2(5)  
 SHEET 13 OF 120

6a 2