

WATER PIPE RELOCATION

NON-GOVERNMENT PARTICIPATION

Lump Sum Bid for relocating water pipe at Sta. 303+25 shall include relocating of water pipe as shown on Plans or as directed by Engineer in the Field, such that existing pipe shall be at least 36" below the lowest point in existing ground or be the lowest point in new construction on the location. It shall include placing new pipe inside a new 24" Galvanized water pipe across the limits of the right-of-way, and shall include construction of a standard shut off valve at the right of the right-of-way and also include connecting new or relocated pipe with additional pipe, as found necessary, to the present pipe at either side of the right-of-way.
 Lump Sum Bid to include all work and materials necessary to perform the work outlined above including all excavating and backfilling.

BM #25
 El. 277.35

BURNHAM
 GALL

BM #25 12" Elm Rt. Sta 301+0 El. 277.35
 BM #26A 18" Willow Lt. Sta. 305+10 El. 304.26

FUTURE IMPROVEMENT

302+50
 V.C. 200'
 292.00

