STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (mm)	SIGN DIMENSIONS HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 3.4	SQUARE STEEL (mm) kg/m 50 3.9	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	FOUND-ATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
												OPTION ITEMS																							
U.S. 7																																			
10+553, RT	TRUCKS ENTERING	1	900	900	0.810						1			3.75																			VW-202		E-154M
11+020, LT	TRUCKS ENTERING	1	900	900	0.810						1			3.75																			VW-202		E-154M
11+070, LT	SCHOOL BUS STOP AHEAD	1	750	750	0.560						1			3.75																			S3-1		E-153M
12+140, LT	SPEED LIMIT 50 M.P.H.	1	600	750	0.450						1			3.75																			R2-1		E-142M
12+140, RT	SPEED LIMIT 50 M.P.H.	1	600	750	0.450						1			3.75																			R2-1		E-142M
13+108, RT	LEICESTER / BRANDON	1	1500	190	0.285						1			3.85																					E-124M
	ADDISON CO. / RUTLAND CO.	1	1500	190	0.285																														E-124M
100+010, RT	SHOULDER MARKERS	1	900	900	0.810						1			3.75																			VW619		E-151M
100+053, LT		1	750	750	0.560						1			3.85																			W2-1		E-155M
	40 M.P.H.	1	450	450	0.200																												W13-1		E-155M
100+053, RT		1	750	750	0.560						1			3.85																			W2-1		E-155M
	40 M.P.H.	1	450	450	0.200																												W13-1		E-155M
100+111, RT		1	750	750	0.560						1			3.75																			S1-1		E-153M
100+205, RT	LEICESTER CENTRAL SCHOOL	1	1350	190	0.260						2			3.68																					E-123M
100205, RT		1	1350	190	0.260																														E-123M
100+281, LT	SOUTH	1	600	300	0.180						1			3.75																			M3-3		E-136AM
												m	m	m	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
											TOTALS	m^2	m^2	EA.	m^2			m		m		kg	EA.		kg			EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: _____

PROJECT NUMBER: _____

FILE NAME: zb05issll.dgn
PROJECT LEADER: _____
DESIGNED BY: M.K. CHEVALIER

PLOT DATE: $$$$DATE$$$
DRAWN BY: M.C. McINTOSH
CHECKED BY: _____
SHEET ___ OF ___