STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) kg/m FOUND-ATION	75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGNS REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
100+281, LT	7	1	600	600	0.36																												MI-4		E-136AM
100+338, RT	NORTH	1	600	300	0.18						1			3.75																			M3-1		E-136AM
100+338, RT	7	1	600	600	0.36																												MI-4		E-136AM
100+414, LT	LEICESTER CENTRAL SCHOOL	1	1350	190	0.26						2			3.68																						E-123M
100+414, LT		1	1350	190	0.26																															E-123M
100+469, LT		1	750	750	0.56						1			3.75																			SI-1		E-153M
100+547, RT	NO PARKING ON TRAVELED LANES	1	600	750	0.45						1			3.75																			VR-020		E-146M
100+564, LT		1	750	750	0.56						1			3.85																			W2-1		E-155M
100+564, LT	40 M.P.H.	1	450	450	0.20																												WI3-1		E-155M
100+820, LT	SPEED LIMIT 50 M.P.H.	1	600	750	0.45						1																									
100+910, LT	SHOULDER NARROWS	1	900	900	0.810									3.75																			VW-619		E-151M
101+069, RT	WATCH FOR TURNING VEHICLES	1	900	900	0.810						1			3.75																			VW-205		E-154M
101+130, RT	[illegible]	1	750	750	0.56									3.75																			WII-6		E-153M
101+580, LT	[illegible]	1	750	750	0.560						1			3.75																			WII-6		E-153M
101+966, RT	WATCH FOR TURNING VEHICLES	1	900	900	0.810						1			3.75																			VW-205		E-154M
102+162, RT		1	750	750	0.56						1			3.75																			WI-2R (MODIFIED)		E-151M
												m	m	m	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS					m²	m²	EA.	m²				m			m					kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S 'SIGN POST DESIGN GUIDELINE.'

PROJECT NAME: _____
PROJECT NUMBER: _____

FILE NAME: zb05issl2.dgn
PROJECT LEADER: _____
DESIGNED BY: M.K.CHEVALIER
PLOT DATE: $$$$DATE$$$
DRAWN BY: M.C. McINTOSH
CHECKED BY: _____