QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

EROSION CONTROL	R.O.W.	BR-100 KING BROOK	BR-110 COW PASS	BR-120 BEAVER MEADOW BROOK	BR-130 BROOK @ STA.296+55	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
									(CONTINUED FROM LAST SHEET)		
									OPTION ITEMS		
						130	130	LF	18" RCP CL III	601.0815	
									18" CPEP (SL)	601.2615	
						68	68	LF	18" CAAP (.060)	601.0215	
									18" PCCSP (.064)	601.0415	
									18" CPEP (SL)	601.2615	
						622	622	LF	18" CAAP (.060)	601.0215	
									18" PCCSP (.064)	601.0415	
									18" RCP CL III	601.0815	
									18" CPEP (SL)	601.2615	
						100	100	LF	18" CAAP (.075)	601.0216	
									18" PCCSP (.079)	601.0416	
									18" RCP CL III	601.0815	
									18" CPEP (SL)	601.2615	
						40	40	LF	24" CSP (.064)	601.0025	
									24" CPEP (.060)	601.2620	
						670	670	LF	24" CAAP (.060)	601.0225	
									24" PCCSP (.064)	601.0425	
						80	80	LF	24" CAAP (.060)	601.0225	
									24" PCCSP (.064)	601.0425	
									24" CPEP (SL)	601.2620	
						340	340	LF	24" CAAP (.060)	601.0225	
									24" PCCSP (.064)	601.0425	
									24" RCP CL III	601.0825	
									24" CPEP (SL)	601.2620	
						316	316	LF	24" CAAP (.075)	601.0226	
									24" PCCSP	601.0426	
						812	812	LF	30" CAAP (.075)	601.0236	
									30" PCCSP (.079)	601.0436	
						132	132	LF	30" RCP CL III	601.0835	
									30" CPEP (SL)	601.2625	
						288	288	LF	30" CAAP (.075)	601.0236	
									30" PCCSP (.079)	601.0436	
									30" RCP CL III	601.0835	
									30" CPEP (SL)	601.2625	
									(CONTINUED ON NEXT SHEET)		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		(CONTINUED FROM LAST SHEET)
		ITEM 406.25 – BITUMINOUS CONCRETE PAVEMENT
		WEARING COURSE – TYPE III
8,659.40	TN	MAINLINE
		BINDER COURSE – TYPE II
7,402.30	TN	MAINLINE
		BASE COURSE – TYPE I
13,334.40	TN	MAINLINE
		WEARING COURSE – TYPE III
37.44	TN	T.H. #49
		BASE COURSE – TYPE I
46.60	TN	T.H. #49
41.33	TN	DRIVES
478.53	TN	ROUNDING
30,000	TN	TOTAL
		ITEM 501.25 – CONCRETE, CLASS B
47	CY	DROP INLETS
	CY	HEADWALLS
RD	CY	ROUNDING
SUB	CY	TOTAL
		ITEM 507.15 – REINFORCING STEEL
3,901	LB	DROP INLETS
	LB	HEADWALLS
99	LB	ROUNDING
4,000	LB	TOTAL
		ITEM 613.10 – STONE FILL, TYPE I
24	CY	CULVERTS
1,242	CY	STONE LINED DITCHES
247	CY	TEMPORARY EROSION CONTROL
37	CY	ROUNDING
1,550	CY	TOTAL
		ITEM 613.11 – STONE FILL, TYPE II
92	CY	CULVERTS
164	CY	STONE LINED DITCHES
7,316	CY	SLOPE STABILIZATION
28	CY	ROUNDING
7,600	CY	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		ITEM 651.35 – TOPSOIL
	CY	MAINLINE
	CY	LAWN AREAS
	CY	ROUNDING
	CY	TOTAL
		ITEM 654.10 – EROSION MATTING
4,447	SY	MAINLINE
22	SY	T.H. #33
989	SY	EROSION CONTROL
42	SY	ROUNDING
5,500	SY	TOTAL
		(CONTINUED ON NEXT SHEET)

STATIONS FROM	STATIONS TO				EQUATIONS +	EQUATIONS –	FEET	MILES	REMARKS
TOTALS									

PROJECT NAME U.S. RTE. 2, MARSHFIELD
PROJECT NUMBER FEGC – F028 – 3(28)

SHEET 13 OF SHEETS