TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS	NEW AND SALVAGED SIGNS "A"	"B"	SALV. SIGN	SALV. T.I.S.	EXISTING POSTS RET.	DRILL	REM	SALV	NEW SIGN POSTS NUMBER OF POSTS	FLANGED CHANNEL LB./FT. 1.12	2.0	2.5	3.0	TUBULAR ALUMINUM 3.0" ø	4.0" ø WALL	3.0" SQ.	4.0" ø	TUBULAR STEEL 3.0"	3.5"	4.0"	5.0"	W-SHAPED STEEL POST SIZE	WEIGHT	FTG. SIZE 24"	30"	SIGN FRAME	REMARKS	PLAN SHEET NUMBER	STD. SHEET NUMBER
138+50 RT		30" X 30"	6.25								1				X														SEE DETAIL B-B, SHEET NO. SEE NOTE # 1		
139+75 RT		30" X 30"	6.25								1				X														SEE DETAIL A-A, SHEET NO.		
140+50 RT		36" X 36"	9.00								1				X																E-151
144+00 LT		36" X 36"	9.00								1				X																E-150
148+00 RT		24" X 30"	5.00								1				X																E-141
152+25 LT		30" X 30"	6.25								1				X														SEE DETAIL B-B, SHEET NO. SEE NOTE # 1		
174+75 RT		30" X 30"	6.25								1				X														SEE DETAIL B-B, SHEET NO. SEE NOTE # 1		
186+60 LT		30" X 30"	6.25								1				X														SEE DETAIL B-B, SHEET NO. SEE NOTE # 1		
245+50 LT		24" X 30"	5.00								1				X																E-141
247+50 LT		24" X 12" 24" X 24"	6.00								1				X																E-136
249+50 RT		24" X 12" 24" X 24"	6.00								1				X																E-136
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE DESIGN DIVISION'S "SIGN POST DESIGN MANUAL".			SF.	SF.	EA.	SF.										1.9 LBS/FT	2.6 LBS/FT	2.5 LBS/FT	2.6 LBS/FT	7.6 LBS/FT	9.0 LBS/FT	10.8 LBS/FT	14.6 LBS/FT								
		TOTALS	71.25																												

PREPARED BY _____ DATE _____
CHECKED BY _____ DATE _____
DESIGN SUPERVISOR _____ DATE _____

U.S. ROUTE 2 – MARSHFIELD
FEGC-F028-3(28)
SHEET 113 OF 352 SHEETS