TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS	NEW AND SALVAGED SIGNS "A"	"B"	SALV. SIGN	SALV. T.I.S.	EXISTING POSTS RET.	DRILL	REM	SALV	NEW SIGN POSTS NUMBER OF POSTS	FLANGED CHANNEL LB./FT. 1.12	2.0	2.5	3.0	TUBULAR ALUMINUM 3.0"	3.0"	4.0"	5.0"	TUBULAR STEEL 3.0"	3.5"	4.0"	5.0"	W SHAPED STEEL POST SIZE	WEIGHT	FTG. SIZE 24"	30"	SIGN FRAME	REMARKS	PLAN SHEET NUMBER	STD. SHEET NUMBER
TH #55 50+55 RT	LEGAL LOAD LIMIT 24,000 POUNDS	24" X 30"	5.00								1				X																E-141
TH #38 60+42 LT	STOP	30" X 30"	5.18								1				X																E-143
TH #38 60+58 RT	LEGAL LOAD LIMIT 24,000 POUNDS	24" X 30"	5.00								1				X																E-141
TH #33 70+36 LT	STOP	30" X 30"	5.18								1				X																E-143
TH #33 70+62 RT	LEGAL LOAD LIMIT 24,000 POUNDS	24" X 30"	5.00								1				X																E-141
TH #34 80+45 LT	STOP	30" X 30"	5.18								1				X																E-143
TH #34 80+45 RT	LEGAL LOAD LIMIT 24,000 POUNDS	24" X 30"	5.00								1				X																E-141
TH #35 90+22 LT	STOP	30" X 30"	5.18								1				X																E-143
TH #35 90+22 RT	LEGAL LOAD LIMIT 16,000 POUNDS	24" X 30"	5.00								1				X																E-141
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE DESIGN DIVISION'S "SIGN POST DESIGN MANUAL".			SF.	SF.	EA.	SF.																									
		TOTALS	275.12			12.00						2154 LBS.																			

TRAFFIC ITEM SUMMARY

ITEM NO.	ITEM	UNIT	QUANTITY	RNDG.	TOTAL
646.40	DURABLE 4" WHITE LINE	LF	55,605.00	1395.00	57,000
646.41	DURABLE 4" YELLOW LINE	LF	46,924.00	1076.00	48,000
646.46	DURABLE 24" STOP BAR	LF	198.00	12.00	210
646.50	DURABLE LETTER IN WORD MKG.	EA	16.00	–	16
675.20	TRAFFIC SIGNS, TYPE "A"	SF	275.12	24.88	300
675.30	FLANGED CHANNEL STEEL SIGN POST	LB	2154.00	96.00	2250
675.50	REMOVING SIGNS	EA	44.00	6.00	50
680.20	TRAVEL INFORMATION SIGNS (MODIFIED)	SF	12.00	–	12

NOTES AND DETAILS:

1. SEASONAL SNOWMOBILE SIGNS

   ITEM 675.20 – SIGNS, TYPE "A": TO BE DELIVERED TO DISTRICT FOR SEASONAL INSTALLATIONS.
   ITEM 675.30 – FLANGED CHANNEL STEEL SIGN POST: TO BE INSTALLED AT PROPER LOCATIONS.

2. REMOVAL OF FLASHING BEACONS, INCLUDING ALL CONNECTIONS TO POWER SOURCE, TO BE PAID FOR UNDER ITEM 675.50 – REMOVING SIGNS.
3. DETOURS TO BE SIGNED AND PAVEMENT MARKED AS PER STANDARD E-107.

TRAFFIC SIGN SUMMARY SHEET

PREPARED BY _____ DATE ____
CHECKED BY _____ DATE ____
DESIGN SUPERVISOR _____ DATE ____

U.S. ROUTE 2 – MARSHFIELD
FEGC-F028-3(28)