

C = 0.50 Ft
F = 764.50 Ft
R = 0.50 Ft

C = 0.50 Ft
F = 731.50 Ft
R = 0.50 Ft

SCALE: 0.05" V.
50.0' H.

C = 27.50 Ft
F = 723.50 Ft
R = 0.50 Ft

STA.	81+00	STA.	82+00
TOWN	MARSHFIELD		
PROJECT	F	NO.	028-3(28)
SHEET	139	OF	352
			SHEETS
			HORIZ. AND VERT. SCALE
			0 10 20
SURVEYED BY:	VT. SURVEY CONSULTANTS	DATE	8/86

BANKING DIAGRAM

ASKED @ 72°-42' RT.

24" R.C.P.

PC #4
Q 81+08.20
D = 7°30'00"
BANK = 0.080 FT/FT

E STA. 81+11 - ASKEWED 72°42' RT.
NEW 36" X 110' P.C.S.P. 0.079' OR
CAMP 0.075'
W/ E.S. C INLET. RAD W/ STN. FILL
TYPE II @ OUTLET 4.5' X 2.0'
EXTENDING 15' BEYOND END OF CULVERT

E STA. 81+11 LT
END STONE LINED
DITCH TYPE I, 6' W

E STA. 81+11 - EXIST. 24" RCP
(TO BE REMOVED)

E STA. 81+00 LT
BEGIN SHOULDER W/ FULL
DEPTH PAVEMENT (8' WIDE)

E STA. 82+00, 5# LT.
BEGIN 6" X 59' CARRIER PIPE.