

DATE	BY
REVISIONS	NO.
FINAL SURVEY	NO.
NO. 1	NO.

VT SURVEY CONSULTANTS	8/86
BRYANT ASSOC.	9/86
NO. 1	NO.
NO. 2	NO.

770
760
750
770
760
750
770
760
750
770
760
750
770
760
750

770
760
750
770
760
750
770
760
750
770
760
750
770
760
750

REV. STA. 93+12 - ASKEWED 82° 28' LT.
NEW 30" X 52" RCP 0.079 OR C&AP 0.075 W/E.S. @
INLET. STONE FILL PAD, TYPE II, @ OUTLET
4' WIDE X 2' DEEP EXTENDING 10'
BEYOND END OF CULVERT.

REV. STA. 93+12 - EXIST. 30" RCP.
(TO BE REMOVED)

REV. 93+11.80 = SURV. 93+11
ASKEWED @ 81° 00' LT.

REV. STA. 92+00 RT.
END LIMIT OF CLEARING & GRUBBING
IS TOP OF BANK (AS SHOWN)

REV. STA. 93+07 RT, 49' RT.
SEG. 6" X 58' CARRIER PIPE

REV. STA. 93+04, 50' RT.
END 6" X 263' U.D. W/FB @
90+50 & 92+70

C = 385 Sq. Ft.
F = 118 Sq. Ft.
R = 0 Sq. Ft.

REV. STA. 93+15 LT.
END 6" X 270' U.D.
W/FB @ STA. 90+50 & 93+00
REV. STA. 93+00 LT.
INSTALL FLUSHING BASIN

REV. 93+00.80 = SURV. 93+00

REV. STA. 92+75 ~ 93+00 RT.
BREAKAWAY CABLE TERMINAL

REV. STA. 92+75 RT.
END STEEL BEAM GUARD RAIL

REV. STA. 92+70 RT.
INSTALL FLUSHING BASIN

C = 137 Sq. Ft.
F = 113 Sq. Ft.
R = 0 Sq. Ft.

REV. STA. 92+25 LT.
END TREATED TIMBER CURB

REV. 92+50.76 = SURV. 92+50

GUARD RAIL FLARE DETAIL

1" = 20'
SCALE

C = 300 Sq. Ft.
F = 68 Sq. Ft.
R = 0 Sq. Ft.

REV. STA. 92+25 LT.
END SLOPE STABILIZATION
W/TYPE II STONE

REV. 92+00.68 = SURV. 92+00

STA.	92+00	STA.	93+11
TOWN	MARSHFIELD		
PROJECT	F	NO.	028-3(28)
SHEET	148	OF	352
		SHEETS	
		HORIZ. AND VERT. SCALE	
		0 10 20	
		VT. SURVEY	
		CONSULTANTS DATE	8/86