

VT. SURVEY CONSULTANTS
BRYANT ASSOC.
10/86
10/86



REV. STA. 153+60 LT
END STONE LINED DITCH
TYPE II, 6' WIDE.
BEGIN EROSION MATTING

REV STA 153+76
BEGIN DRILLING AND
BLASTING OF SOLID ROCK
SUBGRADE

REV STA. 154+10 RT
END REMOVAL & DISPOSAL
OF GUARD RAIL.

REV STA 153+10 LT
END SPECIAL DITCH

C = 38 Sq Ft
F = 472 Sq Ft
R = 0 Sq Ft

C = 1 Sq Ft
F = 908 Sq Ft
R = 0 Sq Ft

REV STA 153+10 RT
NEW 12" X 70" CSP 0.064"
20' ELBOWS TOP + BOTTOM,
NEW PROCD W/CI GRATE @ INLET
STONE FILL TYPE I, PAD @ OUTLET
2' W X 1' D EXTENDING 4' BEYOND
END OF CULVERT.

REV STA 153+07 ASKEWED 85° 00' LT
NEW 24" X 150" PC CSP 0.064" OR
CRAP 0.060" W/
E.S. @ INLET, STONE FILL TYPE II
PAD @ OUTLET 4' W X 2' D EXTENDING
8' BEYOND END OF CULVERT.

REV. STA. 153+02
EXISTING 30" RCP
(TO BE REMOVED)

STA.	153+42	STA.	154+00
TOWN	MARSHFIELD		
PROJECT	F	NO.	028-3(28)
SHEET	198	OF	352
HORIZ. AND VERT. SCALE			
0 10 20			
VT SURVEY			
SURVEYED BY: CONSULTANTS DATE 10/86			

SCALE: 1" = 10'
H & V