

DATE	
BY	
SURVEYED	
PLOTTED	
TEMPERATURE	
WIND	
MOON	
NO. OF SHEETS	
NO.	

DATE	10/86
BY	VT. SURVEY CONSULTANTS
PROJECT	BRANT ASSOC.
SURVEYED	
PLOTTED	
TEMPERATURE	
WIND	
MOON	
NO. OF SHEETS	
NO.	

REV. STA. 205+50 LT.
BEGIN 6" x 553" U.D.
WI. FB. @ 205+50, 209+00 & 210+55
INSTALL FLUSHING BASIN

POLE H. 175
114
SURV. STA. 205+75

C = 0 Sq Ft
F = 421 Sq Ft
R = 0 Sq Ft

REV. STA. 205+40 RT.
END REMOVAL & DISPOSAL
OF GUARD RAIL

SURV. 205+50 = REV. 205+50.35

REV. STA. 205+33 LT. ASKEWED 89°-50' LT.
NEW 18" x 112" RCP CL III
OR OPER (SL) NEW 4' x 4' RCDI W/TYPE A GRATE @
INLET STN. FILL PAD TYPE I @
OUTLET 3' W x 1' D EXTENDING
4' BEYOND END OF CULVERT.
REV. STA. 205+31 LT.
END SPECIAL DITCH

REV. STA. 205+33 LT.
EXISTING 15" RCP
(TO BE REMOVED)
STA. 205+31 LT.
END STONE LINED DITCH 4' WIDE, TYPE I

PC #11
REV. 204+69.33
I = 4' 00' 00"
BANK = 0.063 Ft/Ft

REV. STA. 205+00 LT.
BEGIN SPECIAL DITCH

REV. STA. 205+00 LT.
BEGIN STONE LINED DITCH
4' WIDE W/TYPE I STONE

REV. STA. 204+82 ~ 205+33 LT.
NEW 18" x 30' RCP DITCH
OR C&P 0.060" NEW 4' x 4'
RCDI W/TYPE A GRATE
@ INLET
END PAVED GUTTER

REV. STA. 204+75 LT.
END 10' WIDE PATH

REV. STA. 204+50 ~ 204+82 LT.
NEW 18" x 30' RCP DITCH
OR C&P 0.060" NEW 4' x 4'
RCDI W/TYPE A GRATE
@ INLET
END STONE LINED DITCH,
TYPE II, 6' WIDE

SURV. 205+33 = REV. 205+33.23
ASKEWED @ 89°-50' LT.

C = 0 Sq Ft
F = 329 Sq Ft
R = 0 Sq Ft

REV. STA. 204+75 &
CONSTRUCT LITTLE PASS
SEE PI SHEETS BR-110

SURV. 205+00 = REV. 205+00.00

C = 0 Sq Ft
F = 212 Sq Ft
R = 0 Sq Ft

SURV. 204+50 = REV. 204+49.72

STA.	204+50	STA.	205+50
TOWN	MARSHFIELD		
PROJECT	F NO. 028-3(28)		
SHEET	234 OF 352 SHEETS		
HORIZ. AND VERT. SCALE 0 10 20			
VT. SURVEY CONSULTANTS DATE 10/86			