

REV. STA. 211+31 ~ ASKEWED 61° 17' RT.
NEW 80" X 148" FCCSP 0.019" C.A.P.
0.095" W/E, S. @ INLET.
PAD W/ STN. FILL TYPE II, A.W. X 2' D.
OUTLET EXTENDED 10' BEYOND
END OF CULVERT.

REV. STA. 211+31
EXIST. 24" C.G.M.P.
(TO BE REMOVED)

SURV. 211+19 = REV. 211+31.15
ASKEWED @ 60°-42' RT.

SURV. 211+00 = REV. 211+05.17

SURV. 210+50 = REV. 210+54.82

SURV. 210+00 = REV. 210+04.40

C = 64 Sq Ft
F = 625 Sq Ft
R = 0 Sq Ft

C = 0 Sq Ft
F = 220 Sq Ft
R = 0 Sq Ft

REV. STA. 210+25
BEGIN SCARPING
EXISTING PAVEMENT

C = 0 Sq Ft
F = 35 Sq Ft
R = 0 Sq Ft

REV. STA. 211+00, 40' LT.
END 6" X 553" U.D.
W/ R.B. @ 205+50, 209+00S
210+55
INSTALL FLUSHING BASIN

REV. STA. 210+54 LT
END SPECIAL DITCH

PT #11
REV. 210+45.66
D = 4' 00" 00"
BANK = 0.063 FT. 1 FT.
-0.021 FT. 1 FT.

BANKING DIAGRAM
V.
H.

REV. STA. 210+04 LT
BEGIN SPECIAL DITCH

STA. 210+00	STA. 211+19
TOWN MARSHFIELD	
PROJECT F	NO. 028-3(28)
SHEET 237	OF 362 SHEETS
HORIZ. AND VERT. SCALE	
0 10 20	
VT SURVEY	
CONSULTANTS DATE 10/86	