

EQUALITY
REV 258+68.55 (BK) =
SURV. 258+64.67 (AH)
EQ = +3.88'

C = 6850 Sq Ft
F = 289 Sq Ft
R = 0 Sq Ft

REV STA 258+54 LT
END STONE LINED DITCH
TYPE I B'W.
BEGIN EROSION MATTING

REV 258 + 53.88 = SURV 258 + 50

REV STA 258+20 LT.
INSTALL FLUSHING BASIN

POLE # 133
72
SURV. STA. 258+30

REV STA 257+94 LT
BEGIN STONE LINED
DITCH TYPE I, 6' W

C = 45 Sq Ft
F = 457 Sq Ft
R = 0 Sq Ft

REV 258 + 03.85 = SURV 258 + 00

REV STA 257+98, 45' LT.
BEGIN 6" X 42' U.D. W/ FB @
REV STA. 258+20 & 262+50

REV STA 257+96, 42' LT.
END 6" X 131' U.D. W/ FB @
REV STA 256+75 & 257+80

REV STA 257+85 - ASKEWED 76°51' LT
NEW 24" X 120' R.C.P. @ 0.079" OR
C.A.P. @ 0.075" NEW 4' X 8' ROAD W/ TYPE B
GENE @ INLET, PAD 4' X 4' FULL TYPE II
@ OUTLET 4' WIDE X 2' DEEP EXTENDED 8'
BEYOND END OF CULVERT.

REV STA 257+85
EXIST. 15" R.C.P.
EXIST. 24" C.G.M.P.
(TO BE REMOVED)

REV STA 257+80 LT
INSTALL FLUSHING BASIN

REV 257+85.43 = SURV 257+81
ASKEWED @ 73°-55' LT.

| | | | |
|-----------------------------------|------------|------|------------|
| STA. | 257+81 | STA. | 258+50 |
| TOWN | MARSHFIELD | | |
| PROJECT | F | NO. | 028-3(28) |
| SHEET | 272 | OF | 352 SHEETS |
| HORIZ. AND VERT. SCALE | | | |
| 0 10 20 | | | |
| VT. SURVEY CONSULTANTS DATE 10/86 | | | |

| | |
|-------------------|--|
| DATE | |
| BY | |
| NO. OF SHEETS | |
| NO. OF PAGES | |
| NO. OF PLATES | |
| NO. OF FIGURES | |
| NO. OF TABLES | |
| NO. OF DRAWINGS | |
| NO. OF NOTES | |
| NO. OF REFERENCES | |
| NO. OF OTHERS | |
| NO. OF TOTALS | |

| | |
|-------------------|-----------------------|
| DATE | 10-86 |
| BY | V. SURVEY CONSULTANTS |
| NO. OF SHEETS | 352 |
| NO. OF PAGES | |
| NO. OF PLATES | |
| NO. OF FIGURES | |
| NO. OF TABLES | |
| NO. OF DRAWINGS | |
| NO. OF NOTES | |
| NO. OF REFERENCES | |
| NO. OF OTHERS | |
| NO. OF TOTALS | |