

DATE	
BY	
REVIEWED	
PLOTTED	
TEMPLATE	
AREA CHECKED	
FINAL SURVEY NOTE BOOK NO.	

DATE	
BY	
REVIEWED	
PLOTTED	
TEMPLATE	
AREA CHECKED	
ORIGINAL SURVEY NOTE BOOK NO.	

840
830
820
810
800
790
820
810
800
790
820
810
800
790

830
820
810
800
790
820
810
800
790
820
810
800
790

REV. STA. 271+87.30' LT.
END 8' X 425' U.D. W FB
@ REV. STA. 267+18 E 271+58
REV. STA. 271+86 ASKEWED @ 86°-15' LT.
NEW 18" X 108" PCCBP DIA 4" OR CAAP .060"
NEW 4' X 6' BLDG W/2 TYPE B GRATES @ INLET
PAD W/ STONE FILL TYPE II AT OUTLET
3' W X 2' D. EXTENDED 10' BEYOND
END OF CULVERT.

REV. STA. 271+86
REMOVE EXISTING 15" RCP
REV. STA. 271+58 LT.
INSTALL FLUSHING BASIN

SURV. 271+86 = REV. 271+85.67
ASKEWED @ 86°-15' LT.

SURV 271+50 = REV. 271+49.90

SURV. 271+00 = REV. 271+00.23

REV. STA. 271+50 RT.
END SLOPE STABILIZATION

C = 0 Sq. Ft.
F = 687 Sq. Ft.
R = 0 Sq. Ft.

PC # 16
STA. 271+16.59
D = 1° 50' 26"
BANK = 0.038 FT/FT.

C = 0 Sq. Ft.
F = 606 Sq. Ft.
R = 0 Sq. Ft.

STA. 271+00	STA. 271+87
TOWN	MARSHFIELD
PROJECT	F NO. 028-3(28)
SHEET	281 OF 352 SHEETS
HORIZ. AND VERT. SCALE 0 10 20	
VT. SURVEY SURVEYED BY: CONSULTANTS DATE	