

URBAN TYPICAL SECTIONS

MATERIAL ITEM	THICKNESS TOLERANCE
PAVEMENT	± 1/4"
BASE COURSE	± 1/2"
SUBBASE	± 1"
GRANULAR BORROW	± 1"
SAND BORROW	± 1"

- 1 1/2" BITUMINOUS CONCRETE PAVEMENT TYPE III
- 3" BITUMINOUS CONCRETE PAVEMENT TYPE I
- 24" SUBBASE OF DENSE GRADED CRUSHED STONE
- 6" SAND BORROW (NON-FROST SUSCEPTIBLE MATERIAL) *
- SHOULDERS : 1 1/2" BITUMINOUS CONCRETE PAVEMENT (IN AREAS OF NO CURBING)

*6"-24" OF ADDITIONAL SAND BORROW TO BE USED IN CUT AREAS WHERE UNSUITABLE MATERIAL EXISTS- AS DIRECTED BY THE ENGINEER.





SEEDING FORMULA URBAN AREAS

% WT.	LBS./A.	NAME	PUR%	GERM %
37.50	30	CREeping RED FESCUE	96	85
31.25	25	KENTUCKY BLUE GRASS (COMMON)	85	75
31.25	25	PERENNIAL RYE GRASS (VAR. PENNFILE)	95	90
100.00	80			

NOTE: SEE TYPICAL SECTIONS-1 FOR GENERAL SEEDING NOTES.

GENERAL NOTES

- MARKER POSTS-TO BE PLACED AS DIRECTED BY THE ENGINEER.
- SLOPE ROUNDING-ALL CUT SLOPES TO BE ROUNDED IN ACCORDANCE WITH STANDARD SHEET B-5.
- PAY LIMITS OF SAND BORROW WHEN USED IN CONJUNCTION WITH UNDERDRAIN-SEE STANDARD SHEET D-2
- DRIVE SIDE SLOPES WILL BE TRANSITIONED FROM 1-8 IN THE CLEAR ZONE TO EXISTING CONDITIONS AT THE MATCH LINE.
- THE DRIVEWAY OPENING RADIUS WILL BE 20 FT. UNLESS OTHERWISE SHOWN OR NOTED.



POWNA
RS 0107 (7)

TYPICAL SECTIONS-2

CHECKED BY _____ DATE _____ SHEET 5 of 319

PARE ENGINEERING CORPORATION
Engineers - Planners - Landscape Architects
5 Blackstone Valley Place, Lincoln, RI 02865
401/334/4100