TRAFFIC SIGN SUMMARY SHEET - REMOVAL OF EXISTING SIGNS

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS	EXISTING SIGNS TO BE SALVAGED: REMOVE (EA.)	REMOVE (X)	RETAIN (X)	NEW AND SALVAGED SIGNS: NEW "A" (S.F.)	NEW "B" (S.F.)	SALV. SIGN (EA.)	SALV. T.I.S.(S.F.)	EXISTING POSTS: RET.	DRILL	REM.	SALV.	NEW SIGN POSTS: NUMBER OF POSTS	FLANGED CHANNEL: 2.0 LB./FT.	2.5 LB./FT.	3.0 LB./FT.	TUBULAR ALUMINUM: 3.0" Ø	3.0" □	4.0" Ø	4.0" Ø MOD.	W SHAPED STEEL: POST SIZE	WEIGHT	FTG. SIZE 24"	FTG. SIZE 30"	REMARKS	FOR SIGN DETAIL SHEET: PLAN SHEET NUMBER	STD. SHEET NUMBER
73+40 LT.	STOP	N.A.	1																									
125+40 10' RT.		N.A.	1																									
125+40 10' RT.	35 MPH	N.A.	1																									
142+00 26' LT.		N.A.	1																									
142+00 26' LT.	35 MPH	N.A.	1																									
148+40 RT.		N.A.	1																									
149+00 4' RT.	REDUCED SPEED AHEAD	N.A.	1																									
153+60 23' RT.	SCHOOL BUS STOP AHEAD	N.A.	1																									
154+10 24' RT.	NORTH POWNAL	N.A.			X									1		X												
156+30 5' LT.	HIDDEN DRIVE RIGHT	N.A.	1																									
159+50 16' RT.	SPEED LIMIT 35	N.A.	1																									
159+50 16' LT.	SPEED LIMIT 50	N.A.	1																									
164+85 3' LT.		N.A.	1																									
171+40 14' LT.	SCHOOL BUS STOP AHEAD	N.A.	1																									
189+20 25' RT.	SPEED LIMIT 35	N.A.	1																									
189+30 10' LT.	SPEED LIMIT 35	N.A.	1																									
197+13 8' RT.	25 MPH	N.A. N.A.	1 1																									
198+50 7' LT.	POWNAL HISTORICAL SIGN	N.A.			X					X(2)																		
199+96 32' RT.	RR X-ING	N.A. N.A.	1 1																									
200+20 80' RT.	LEGAL LOAD 24000 LBS.	N.A.	1																									
200+20 RT.	346	N.A.	3																									
200+36 RT.	← POWNAL CTR. 3 POWNAL 4 → 346	N.A.	4																									
200+30 RT.	STOP	N.A.	1																									
SUB-TOTALS			29																									

PARE ENGINEERING CORPORATION
Engineers – Planners – Landscape Architects
8 Blackstone Valley Place, Lincoln, RI 02865
401/334/4100

FINAL LENGTHS ARE TO BE DETERMINED IN THE FIELD, POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE DESIGN DIVISION'S "SIGN POST DESIGN MANUAL".

PREPARED BY _____ DATE _____
CHECKED BY _____ DATE _____
PROJ. POWNAL NO. RS0107(7)

TRAFFIC SHEET NO. _____ SHEET 98 OF 319

1986