TRAFFIC SIGN SUMMARY SHEET - NEW SIGNS

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS	EXISTING SIGNS TO BE SALVAGED: REMOVE (EA.)	REMOVE (X)	RETAIN (X)	NEW AND SALVAGED SIGNS: NEW "A" (S.F.)	NEW "B" (S.F.)	SALV. SIGN (EA.)	SALV. T.I.S. (S.F.)	EXISTING POSTS: RET.	DRILL	REM.	SALV.	NEW SIGN POSTS: NUMBER OF POSTS	FLANGED CHANNEL: 2.0 LB./FT.	2.5 LB./FT.	3.0 LB./FT.	TUBULAR ALUMINUM: 3.0" Ø	3.0" □	4.0" Ø	4.0" Ø MOD.	W SHAPED STEEL: POST SIZE	WEIGHT	FTG. SIZE 24"	FTG. SIZE 30"	REMARKS	FOR SIGN DETAIL SHEET: PLAN SHEET NUMBER	STD. SHEET NUMBER
139+00 28' LT	WATCH FOR FALLEN ROCK	30" x 30"				6.3								1			X											
153+00 28' RT	SCHOOL BUS STOP AHEAD	30" x 30				6.3								1		X												
159+50 33' RT	REDUCED SPEED AHEAD	24" x 30"				5.0								1		X												E-142
163+60 33' RT	SPEED LIMIT 35	24" x 30"				5.0								1		X												E-142
165+55 27' LT	SPEED LIMIT 50	24" x 30"				5.0								1		X												E-142
170+75 27' LT	STOP	24" x 24"				4.0								1	X													E-143
172+00 28' LT	SCHOOL BUS STOP AHEAD	30" x 30"				6.3								1		X												
199+50 35' LT	SOUTH	24" x 12"				2.0								—		—												E-136
199+50 35' LT	346	30" x 24"				5.0								1		X												E-136
200+60 35' RT	STOP	30" x 30"				6.3								1		X												E-143
201+20 28' RT	NORTH	24" x 12"				2.0								—		—												E-136
201+20 28' RT	346	30" x 24"				5.0								1		X												E-136
203+05 35' RT	STOP	24" x 24"				4.0								1		X												E-143
207+70 27' RT	SPEED LIMIT 50	24" x 30"				5.0								1			X											E-142
205+05 28' LT	SHOULDER NARROWS	36" x 36"				9.0								1			X											E-151
214+00 27' LT	REDUCED SPEED AHEAD	24" x 30"				5.0								1			X											E-142
220+80 35' RT	STOP	24" x 24"				4.0								1			X											E-143
222+50 27' RT	SPEED LIMIT 50	24" x 30"				5.0								1			X											E-142
234+50 28' RT	R R	36" DIA.				7.1								1			X											E-190
203+00 27' LT	SPEED LIMIT 35	24" x 30"				5.0								1		X												E-142

249+50 28' LT	R R	36" DIA.				7.1								1			X											E-190
250+00 50' RT	NEW YORK STATE LINE	8'-6" x 4'-0"				34.0											X											
SUB-TOTALS						143.4									1	10	9											

FINAL LENGTHS ARE TO BE DETERMINED IN THE FIELD, POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE DESIGN DIVISION'S "SIGN POST DESIGN MANUAL".

PAICE ENGINEERING CORPORATION
Engineers — Planners — Landscape Architects
8 Blackstone Valley Place, Lincoln, RI 02865
401/334/4100

STD. SHEET NO. E-144

PREPARED BY _____ DATE _____
CHECKED BY _____ DATE _____

PROJ. PONNAL VT. 346 NO. RS0107(7)

TRAFFIC SHEET NO. _____ SHEET 102 OF 319