STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
RUPERT: 0+222.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			4.1 X			X																			E-141M
0+224.0, LT	DORSET WEST RD						1				1		X	3.6		X																	SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
	STOP	1	750	750	0.56						1			4.0 X			X																			E-143M
0+225.0, LT	STOP 0300 0210 0015	1 1	750 150	750 200	0.56 0.03		1	STOP			1			4.1 X			X																	BACK-TO-BACK		E-143M E-138M
0+238.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			4.1 X			X																			E-141M
3+815.5, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			3.8 X			X																			E-141M
3+817.0, RT	STOP	1	750	750	~~0.56~~						1			X			X																			E-143M
3+820.0, RT	SYKES HOLLOW RD						1				~~1~~		X			X																	SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
830.0 3+~~835.0~~, RT	STOP 0300 0210 0237	1 1	750 150	750 200	0.56 0.03						1		4.1																				BACK-TO-BACK		E-143M E-138M
4+384.0, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			3.8 X			X																			E-141M
4+395.0, RT	STOP 0300 0210 0273	1 1	750 150	750 200	0.56 0.03						1			4.1 X			X																	BACK-TO-BACK		E-143M E-138M
4+396.0, RT	HERRICK BROOK RD						1				1		X	3.8		X																	SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
												m	m	m	m	m	m	EA	kg	kg	kg		kg	kg	kg	kg								
													~~9.2~~	39.5 42.1		~~9.2~~	~~42.1~~																		
TOTALS		m^2 ~~4.69~~ 4.13	m^2	EA ~~3~~ 4	m^2							m ~~51.3~~ 39.5			m ~~51.3~~				kg	EA	kg		EA	EA	kg								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
RUPERT - PAWLET	STP 2133(I)S

DESIGN FILE NAME: /pave/00b048/pb048.dgn
IPARM FILE NAME: pb048tssl.i
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 4/01
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 27 OF 40