STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

APPROXIMATE SUMMARY OF QUANTITIES

R.O.W.	EMPLOYEE TRAINEESHIP	FULL CE	GOV'T PARTICIPATING BRIDGE	GOV'T PARTICIPATING ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				650	650	CY	EARTH BORROW	203.30	EST
				1	1	CY	TRENCH EXCAV. OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST
				900	900	SY	COLD PLANING - BITUMINOUS PAVEMENT	210.10	60
				250	250	TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	EST
				2,300	2,300	TON	AGGREGATE SHOULDERS	402.12	10
				400	400	CWT	EMULSIFIED ASPHALT	404.65	EST
				10,800	10,800	TON	MEDIUM DUTY BIT. CONCRETE PAVEMENT (PG 58-34)	406.27	260
				1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	406.28	--
				1	1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	406.29	--
				1	1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	406.30	--
				1	1	LU	LONGITUDINAL JOINT COMPACT. PAY ADJ. (N.A.B.I.)	406.31	--
				1	1	LU	PRICE ADJ. ASPHALT CEMENT (N.A.B.I.)	406.50	--
				80	80	FT	15" CPEP	601.0910	--
				5	5	EA	REHABILITATION OF D.I., C.B. OR M.H. CLASS I	604.412	EST
				70	70	HR	POWER GRADER RENTAL	608.15	EST
				110	110	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
				60	60	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
				220	220	HR	TRUCK RENTAL	608.37	EST
				90	90	HR	LOADER RENTAL, TYPE I	608.40	EST
				250	250	CY	STONE FILL, TYPE I	613.10	20
				2	2	EA	YIELDING MARKER POST	619.17	EST
				4,600	4,600	FT	STEEL BEAM GUARD RAIL, GALVANIZED	621.20	9.5
				6,025	6,025	FT	STEEL BEAM GUARD RAIL, GALVANIZED W/8' POSTS	621.205	3
				24	24	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50	--
				2	2	EA	MANUFACTURED TERMINAL SECTION, TANGENT	621.51	--
				4	4	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	--
				10,800	10,800	FT	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	37
				100	100	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
				2,200	2,200	HR	FLAGGERS	630.15	EST
		1			1	LS	FIELD OFFICE, ENGINEERS	631.10	--
		1			1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	--
		1			1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	EST
				1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	EST
				1	1	LS	TRAFFIC CONTROL	641.10	EST
				59,000	59,000	FT	DURABLE 4 IN WHITE LINE, THERMOPLASTIC	646.402	--
				53,000	53,000	FT	DURABLE 4 IN YELLOW LINE, THERMOPLASTIC	646.412	--
				40	40	FT	DURABLE 24 IN STOP BAR, THERMOPLASTIC	646.482	--
				8	8	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	--
				59,000	59,000	FT	TEMPORARY 4 IN WHITE LINE, PAINT	646.602	EST
				52,500	52,500	FT	TEMPORARY 4 IN YELLOW LINE, PAINT	646.612	EST

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
200	SY	BEGIN PROJECT
340	SY	TOWN HIGHWAYS
100	SY	DRIVES
200	SY	END PROJECT
60	SY	ROUNDING
900	SY	TOTAL
		MEDIUM DUTY BIT. CONCRETE PAVEMENT (PG 58-34)
		TYPE IV (LEVELING)
360	TON	GREENSBORO
870	TON	WHEELOCK
670	TON	GREENSBORO
1,930	TON	GLOVER
140	TON	RUNAWAY POND REST AREA/PULL OFF
		TYPE IV (WEARING)
600	TON	GREENSBORO
1,440	TON	WHEELOCK
1,110	TON	GREENSBORO
3,220	TON	GLOVER
140	TON	RUNAWAY POND REST AREA/PULL OFF
30	TON	TOWN HIGHWAYS
30	TON	DRIVES
260	TON	ROUNDING
10,800	TON	TOTAL
		SUBBASE OF CRUSHED GRAVEL (FINE GRADED)
250	TON	ESTIMATED QUANTITIES FOR DRIVES/TH'S
250	TON	ESTIMATED TOTALS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS

TOTALS

QUANTITY SHEET #1

PROJECT NAME **GREENSBORO - GLOVER** p00B056.dgn
PROJECT NUMBER **STP 2226(1)S** p00B056qsl.i

DATE PLOTTED 15-MAY-2008 14
SHEET **4** OF **19** SHEETS